


A COURSE IN  
MECHANICAL DRAWING

---

LOUIS ROUILLION


















# A COURSE IN MECHANICAL DRAWING

FOR SCHOOL USE AND FOR SELF-INSTRUCTION  
A PRACTICAL TREATISE ON THE ART OF MAKING  
WORKING DRAWINGS, LETTERING AND DIMENSIONING

BY  
**LOUIS ROUILLION, B.S., A.M.**  
DIRECTOR MECHANICS INSTITUTE, NEW YORK CITY; AUTHOR OF "DRAFTING OF CAMS,"  
"ECONOMICS OF MANUAL TRAINING," ETC., ETC.



FIFTEENTH EDITION, REVISED AND ENLARGED

NEW YORK  
THE NORMAN W. HENLEY PUBLISHING CO.  
2 WEST 45TH STREET  
1922

ENT  
HARBOUR  
VIA

COPYRIGHTED, 1921  
THE NORMAN W. HENLEY PUBLISHING CO.

COPYRIGHTED, 1896  
THE PRANG COMPANY

*Printed in the U. S. A.*

## PREFACE

THIS course in Mechanical Drawing is the result of a number of years' work with evening classes, and has been evolved from a careful study of the needs of such classes. The course was originally issued in blue-print form, with accompanying typewritten notes. In this form it has been in use at Pratt Institute and other schools, and in Y. M. C. A. classes, for some years. In a modified form it has appeared serially in "Machinery."

The course covers a period of two school years of about twenty-four weeks each. Either two or three evenings a week may be devoted to the work. In the former case it may be found necessary to abridge

November, 1921

the number of simple working drawings. The first twenty-four sheets constitute the work of the first year, and sheets XXV-XXIX that of the second year.

Because of the interest in Isometric Drawing evinced by pupils, this subject has been added to the present edition. Isometric Drawings—Sheets XXX-XXXII may advantageously follow Sheet XIII in the first-year course.

The exercises given at the end of the book, form a parallel independent course permitting the use of the book as a text-book in class work.

All drawings shown in this book are the work of students.

LOUIS ROUILLION.

459219

621.004

5102



# CONTENTS

---

	PAGE		PAGE
<b>GENERAL INSTRUCTIONS.</b>		Sheet VII.	Door Joint, . . . . . 24
Required Materials, . . . . .	1	Sheet VIII.	Development of a Cube, . . . . 26
Use of Materials, . . . . .	2	Sheet IX.	Development of a Square Pyramid, . 28
Drawing Board—Paper—T-Square—Triangles		Sheet X.	Development of a Truncated Hexa-
— Compasses — Drawing Pen — Pencils —			gonal Prism, . . . . . 30
Scroll — Scale — Ink.		Sheet XI.	Development of a Cylinder, . . . 32
Lettering, . . . . .	7	Sheet XII.	Development of a Cone, . . . . 34
Models, . . . . .	8	Sheet XIII.	Development of a Four-Piece Elbow. 36
 <b>REGULAR COURSE.</b> 		Screw Threads, . . . . .	38
Sheet I.	12	Sheet XIV.	Screw Threads, . . . . . 40
Sheet II.	14	Sheet XV.	Springs, . . . . . 42
Sheet III.	16	Sheet XVI.	Bolts and Nuts, . . . . . 44
Sheet IV.	18	Sheet XVII.	Wrench, . . . . . 46
Sheet V.	20	Sheet XVIII.	Seven-inch Pulley, . . . . . 48
Sheet VI.	22	Sheet XIX.	Cone Pulley, . . . . . 50
		Sheet XX.	Flange Coupling, . . . . . 52

# CONTENTS—Continued.

	PAGE		PAGE
Sheet XXI. Pillow Block, . . . . .	54	Sheet XXV. Assembly Drawing of a Bench Lathe	70
Sheet XXII. Clamp, . . . . .	56	Sheet XXVI. Details of Head-Stock, . . . .	72
Sheet XXIII. Monkey Wrench, . . . . .	58	Sheet XXVII. Details of Tool-Rest, . . . .	74
Sheet XXIV. Globe Valve, . . . . .	60	Sheet XXVIII. Details of Tail-Stock, . . . .	76
Notes on Working Drawings, . . . . .	63	Sheet XXIX. Details of Bed, . . . . .	78
1. Size of Sheets—2. Title, Index, etc.—		Sheet XXX. Isometric Drawing . . . . .	80
3. Sketches—4. Laying-out Work—5. Relation of Views—6. Sectioning—7. Inking		Sheet XXXI. Isometric Drawing of Face Plate .	82
—8. Dimensioning—9. Tracings—10. General Notes.		Sheet XXXII. Use of Isometric Paper, . . . .	84
Blue Printing, . . . . .	67		
		PARALLEL COURSE	
		Exercises I-XXIX, . . . . .	89

# COURSE IN MECHANICAL DRAWING.

## GENERAL INSTRUCTIONS.

### REQUIRED MATERIALS.

In order that acceptable work may be accomplished, fairly good instruments should be provided. The cheap brass sets that are sometimes offered by dealers for use in schools are worse than useless. The advice

of some one experienced in draughting instruments should be sought before purchasing. The following list of materials required for this course gives approximate prices that may be considered as inexpensive as it is advisable to obtain.

### LIST OF MATERIALS.

Drawing board, about 16 x 23 inches .	\$1.00 ✓	Pencil . . . . .	\$ .05 ✓
Compasses, 5½ inches, with needle point,		12-inch boxwood scale, flat, graduated	
pen, pencil and lengthening bar .	2.00 ✓	to ⅛ inch the entire length . .	.40 ✓
Drawing pen, 4½ inches . . . . .	.70 ✓	Bottle of liquid India ink . . . . .	.25
T-square, 24-inch blade . . . . .	.45 ✓	Tacks . . . . .	.05 ✓
45° triangle, 9 inches . . . . .	.45 ✓	Pencil and ink eraser . . . . .	.05 ✓
30°-60° triangle, 11 inches . . . . .	.40		<u>\$6.30</u>
Celluloid scroll . . . . .	.50 ✓	Drawing paper.	

**USE OF MATERIALS.**

**DRAWING BOARD.** A light board having a smooth surface and the left-hand edge trued perfectly straight will serve as a drawing board. It should be somewhat larger than the largest sheet of paper that is to be used upon it. The left-hand edge serves as a guide for the head of the T-square. The left and right-hand edges should be composed of narrow strips, the grain of which runs across that of the board.

**PAPER.** The drawing paper should have a surface that will permit of considerable erasing without becoming roughened. When working by artificial light it is desirable that the paper be of a light-brown color which is less trying to the eyes than a pure white. Paper may be purchased in sheets 22 x 30 inches, that make four exercise sheets, each measuring 11 x 15 inches.

The sheet is tacked upon the board as shown in the Diagram opposite (Fig. 1),

being placed well over towards the left-hand side of the board, thus permitting greater firmness in the use of T-square and triangles.

Thumb tacks may be used for securing the paper to the board, or one-ounce tacks, which should be driven well into the board. These latter have the advantage of offering less obstruction to the use of the T-square. When large sheets are used and the drawing requires considerable time, the paper may be stretched upon the board.

The paper is stretched by turning up about an inch of the paper all around the edge and thoroughly wetting the trough thus formed. The edge is turned up to keep it dry, so that it may be used for glueing. See that the edge is firmly glued to the board. When the paper is dry it will be found to be smoothly stretched. When the drawing is completed, the sheet may be cut out with a sharp knife. The T-square or triangle should not be used as straight-edges for trimming sheets.



DRAWING-BOARD, T-SQUARE AND TRIANGLES.




FIG. 1.

**T-SQUARE.** The head of the T-square is always kept against the left-hand edge of the board and its upper edge is used in drawing all horizontal lines and for resting the triangles upon.

**TRIANGLES.** The triangles are used in drawing all straight lines other than horizontal ones. They are rested upon the upper edge of the T-square, and thus afford means of drawing vertical lines and lines at  $30^\circ$ ,  $45^\circ$  and  $60^\circ$ . By placing one triangle upon the other, angles of  $15^\circ$  and  $75^\circ$  may be obtained. A perpendicular may be drawn to any line situated at an angle other than those mentioned, by placing either triangle upon the other so that its hypotenuse coincides with the line, and then revolving it through an angle of  $90^\circ$ .

**COMPASSES.** The compasses are supplied with needle-points, pen and pencil, and are used for drawing circles and arcs of circles. By placing needle-points in each of the legs,

the compasses may be used as dividers in stepping off distances. Supposing it is required to divide a given line into seven equal parts. The compasses are opened to an approximation to one of the parts and seven of these parts are stepped off lightly, without puncturing the paper. The error is noted and the compasses reset to a closer approximation, and the process continued until the required division is obtained. The paper is then lightly punctured at each step. The line may be either straight or curved. Determining a point by a needle prick has the advantage over a pencil-point in that it is not lost by erasure, and is more accurately determined. The position of the point is emphasized by drawing a small circle in pencil about it.

For penciling circles or arcs of circles, the pencil is placed in one leg of the compasses and the needle-point in the other. The legs should be bent at the joints until the lower extremities are parallel, or nearly so. The

compasses are held at the joint, rotated clockwise, and inclined slightly in the direction of the line. A slight pressure is exerted. In inking, the pen is substituted for the pencil, and the weight of the compasses is sufficient to cause the ink to flow.

**DRAWING PEN.** The pen is filled by dropping the ink between the nibs while held in a nearly vertical position.

In inking, the pen is held between the thumb and forefinger. Care should be taken that the nibs are not pressed together while the pen is thus held, as a line of varying thickness would result.

The flat side of the point is laid against the edge of the T-square or triangle and the pen held within the plane of that edge. The taper to the point is sufficient to throw it far enough from the edge to prevent blotting. The handle should be tilted about  $35^\circ$  to the right of perpendicular. Draw from left to right and from the bottom to the top. The

breadth of a line may be controlled by the adjusting screw.

If the pen is not in use, even for a short time, the ink should be taken out, as it evaporates quickly and clogs the pen. For this purpose, pass the corner of a piece of chamois skin between the nibs of the pen. Keep the nibs of the pen at all times bright and clean.

**PENCILS.** A soft pencil, sharpened to a round point, should be provided for putting in letters, figures, arrow-heads and other free-hand work, and for making sketches. A hard pencil, sharpened to a flat chisel-like edge, should be used for drawing all lines with the aid of the instruments. The pencil should be used lightly, so as not to indent the paper. A small flat file, or a piece of fine sand-paper should be at hand, over which the pencil may be occasionally rubbed. For erasing pencil marks, a soft rubber should be provided, and a hard or sand rubber for erasing ink.

**SCROLL.** The scroll is used in obtaining curves other than arcs of circles. If a curve is to be passed through a number of predetermined points, it should first be sketched in lightly free-hand. A section of the scroll is then applied to the curve so as to embrace as many points as possible. Only the central points of those thus embraced should be inked in. This process is continued until the desired curve is completed.

**SCALE.** When practicable, objects should be drawn full size. When an object is too large to permit of this, it may be drawn to the largest convenient scale. With the measuring scale recommended for this course drawings may be made to half or quarter scale. By half-scale is meant that each half-inch upon the drawing represents a full inch upon the object. A special scale may be made as follows: Supposing it is desired to make a drawing to five-eighths scale; that is, that each inch upon the object will be represented by five-eighths

of an inch upon the drawing. Take a slip of paper and measure off upon its edge five-eighths of a foot. Divide this distance into twelve equal parts, and each of these divisions into halves, quarters and eighths. In using such a scale treat it as though it were a full scale; *e. g.*, if the object being drawn measures  $11\frac{1}{2}$  inches, read  $11\frac{1}{2}$  inches from the reduced scale, make the drawing accordingly, and dimension as  $11\frac{1}{2}$  inches.

**INK.** The liquid India ink that comes in bottles is generally used for school work, and answers all requirements. Some draughtsmen prefer the stick ink, which gives somewhat better results, but requires preparation. Black ink alone should be used, except on tracings where lines that may be printed lightly, as dimension and construction lines, may be in red ink. Do not place too much ink between the nibs of the pen. A column of from one-quarter to three-eighths of an inch high is all that should be used at a time.

**LETTERING.**

It is desirable to confine the lettering of drawings to one or two standard alphabets that are plain and distinct, and the principles of which are easily acquired. These conditions are fulfilled in the Gothic fonts shown in Fig. 2. To analyze each letter and study its correct proportions and relations to other letters under varying combinations, would consume more time than can be allotted in this course. Therefore, a simple expedient may be resorted to, by which all the capitals, with the exception of I, J, M, and W, may be considered as having the same breadth. This breadth should be about five-sixths of the height. The inclination of the slant letters is about 20 degrees to the right of perpendicular. The upper parts of letters are made slightly smaller than the lower parts. The basis of the curved lower-case letters of the vertical font is a circle. Other characteristics may be noted by a careful inspection of the examples given.

All lettering should be free-hand. Keep the pencil sharpened to a fine, round point. If the lettering is to be done in ink, a common writing-pen may be employed, or the drawing pen may be used as an ordinary pen.

The titles for the sheets given on the following pages are composed of  $\frac{1}{8}$ -inch letters. The O of the lower-case has a diameter of  $\frac{1}{8}$  inch.

In putting the title upon a sheet, first draw two lines  $\frac{1}{8}$  inches apart along the edge of a slip of paper and sketch in the title, to ascertain the amount of room it will occupy. Then draw lightly upon the sheet,  $\frac{3}{4}$  inches below the top marginal line, two horizontal lines  $\frac{1}{8}$  inches apart, and the central vertical line of the sheet. Fold the slip of paper so that the end letters of the title will coincide.

The fold will then be the centre point of the title. Lay the slip directly below the lines drawn on the sheet, so that the centre point of the sketched title will coincide with the centre line of the sheet. The location of

the title is thus quickly determined and may now be carefully drawn, using the sketch as a guide.

The dimension-figures should be a scant eighth-inch in height. The division line of fractions should be parallel to the direction of the dimension line.

### MODELS.

Geometric models are chosen as the subjects for the earlier exercises, as they are so simple in form. Moreover as types of all

forms, they present the underlying forms in mechanical construction, however complex that construction may be. They serve, then, not only as simple models for elementary practice, but also as giving the form basis for the most advanced work. The geometric models presented are—cube, equilateral triangular prism, hexagonal prism, square pyramid, cone, hollow cylinder, truncated hexagonal prism, and cross. It will be well for students to study the models and objects in making the drawings.

## Freehand Lettering.

A B C D E F G H I J K L M N O P Q R S T U V W X Y Z

1 2 3 3 4 5 6 7 8 9 0 & &

a b c d e f g h i j k l m n o p q r s t u v w x y z

A B C D E F G H I J K L M N O P Q R S T U V W X Y Z

1 2 3 3 4 5 6 7 8 9 0 & &

a b c d e e f g h i j k l m n o p q r s t u v w x y z

Use this style for Headings, etc.

*Use this style for Notes and Dimensions.*

FIG. 2

## Construction of Freehand Lettering.

A B C D E F G H I J K L M N O P Q R S T U V W X Y Z

1 2 3 4 5 6 7 8 9 10 11 12

a b c d e f g h i j k l m n o p q r s t u v w x y z

A B C D E F G H I J K L M N O P Q R S T U V W X Y Z

1 2 3 4 5 6 7 8 9 10 11 12

a b c d e f g h i j k l m n o p q r s t u v w x y z

*Note: Arrows indicate direction of pen strokes.  
Numbers show the order in which strokes are to be made.*



## **REGULAR COURSE**

# REGULAR COURSE EXERCISES.

## SHEET I.

### Cubes — Top and Front Views.




This sheet gives the top and front views of a cube in three positions — facing, turned at  $45^\circ$ , turned at  $60^\circ$  and  $30^\circ$ . At the left of the sheet the top and front views of the cube facing are shown. Draw a 2-inch square as shown in the upper left-hand corner, using the upper edge of the T-square for the top and bottom lines and a triangle resting upon the T-square for the sides. This is the top view of the cube facing. Continue the vertical lines below the lower horizontal line, the top view thus obtaining the side lines of the front view, and draw the top and bottom lines two inches apart. The two views required are now completed. After the drawing is finished the dimensions should be put on. As a cube has length, breadth and depth, three measurements should be given. The length and breadth are here shown on the front view and the depth on the top view.

In the centre of the sheet two views of the cube turned at an angle of  $45^\circ$  are shown. The top view

must first be drawn and is obtained with the  $45^\circ$  triangle. From the corners lines are dropped as in the first case and the top and bottom lines are drawn, completing the front view.

At the right of the sheet, two views of the cube turned at  $60^\circ$  and  $30^\circ$  are shown. The top view is turned so as to form angles of  $60^\circ$  and  $30^\circ$  with the horizontal. The  $60^\circ$  and  $30^\circ$  triangle is used in drawing this view. The front view is obtained as in the previous cases. It will be seen that whereas in the second case the front and back edges of the cube coincide in the front view, in this case the back edge falls to the right of the front edge and is hidden. This is shown by putting in the back edge with a broken line, called a "hidden line." The lines here used in showing the relation of the top and front views are called "construction lines," made up of dashes a scant  $\frac{1}{8}$  inch in length. Directions for drawing hidden lines are given on page 66.

## CUBES



**SHEET II.****Triangular and Hexagonal Prisms.**



Prisms are solids having their ends parallel, and the edges formed by their sides parallel, and are known as triangular, hexagonal, etc., from the form of their bases. Before making the drawings, consider how to place them well upon the sheet.

Two views of the equilateral triangular prism are given. First draw the equilateral triangle for the top view, using the  $60^\circ$  triangle for the sides, and complete the two views to the dimensions given.

In the case of the hexagonal prism, three views are shown: the top, front and left-hand views. To obtain these, first draw a hexagon with  $1\frac{1}{2}$  inch sides for the

top view. This is done by drawing the lower line and cutting off the desired length. Then with the  $60^\circ$  triangle draw the lower side lines and cut off  $1\frac{1}{2}$  inches. The upper side lines are also drawn with the same triangle and the hexagon is completed by adding the top line. The front view is obtained as in the case of the triangular prism. The height in the side view is the same as in the front view, and distances from side to side are obtained directly from distances from top to bottom in the top view. This relation of the top and side views is shown in the drawing by the construction lines.

## TRIANGULAR AND HEXAGONAL PRISMS



## SHEET III.

## Projection of Square Pyramid.


This sheet shows the relation of the various views of an object and the proper method of projecting one view from another.

First draw the base line of the pyramid in the front view at an angle of 30 degrees to the horizontal and cut off the required length of two inches. At the centre of this base line erect a perpendicular to it to serve as a centre line. This is drawn with the 60-degree triangle. Mark off on this centre line a distance of four inches from the base line. Join this point with the extremities of the base line, completing the front view. At a suitable distance, say two inches, above this view, draw a horizontal line as the centre line of the top view, and one inch on either side draw lines parallel to it. Complete the foreshortened view of the base by drawing vertical lines upward from the extremities of the base line of the front view. The apex of the pyramid is on the centre line. The point is determined by drawing a vertical line from the apex in the front view, and is where this line intersects the centre line. Complete the top view by joining the apex to the corners of the base.

To obtain the left-hand view, first draw the vertical centre line at a convenient distance to the left of the front view. This centre line corresponds with the centre line shown in the top view, therefore all distances above the centre line in the top view are equal to distances to the left of the centre line in the left-hand view, and distances below the centre line in the top view are equal to distances to the right of the centre line in the left-hand view. As in **Sheet II** these relations are shown by construction lines. For the base line, therefore, measure off one inch either side of the centre line, and erect perpendiculars for the sides of the base. Cut off the required length by projecting a horizontal line from the tilted-up corner of the base in the front view, and complete the view as in the case of the top view. The right-hand view is obtained in a similar manner.

In inking, show all edges that are actually seen, by full, strong lines. Where an edge is hidden by a face in front of it, show it by "hidden lines." Centre lines are drawn lightly, and are made up of dashes alternately one-half and one-eighth inches long.

*PROJECTION of SQUARE PYRAMID*



**SHEET IV.****Projection of Cross.**

This sheet emphasizes the method of projecting one view from another, and shows how any one view may be obtained directly from two other views by this means, and also how a view is rotated so as to show three sides.

Draw the top and front views of a cross to the dimensions given as shown at the left of the sheet.


For the central group, tip the front view  $30^\circ$  to the right, and obtain the top view by projecting similar points from this view and the top view of the left-hand group. Care should be used in getting the hidden lines correctly.

In the left-hand group the cross is shown standing erect on its base and squarely facing the observer. In

the central group it is shown still facing the observer, but tilted to the right. In the right-hand group it is desired to show the cross turned  $30^\circ$  away from the observer, while still tilted as before. The turning of an object about a perpendicular axis may be shown by turning the top view in the desired direction and through the desired angle.

Therefore, as we want to show the cross turned away at an angle of  $30^\circ$ , we rotate the top view through the required angle. The final view is obtained from this rotated top view and the front view of the central group. One face A B C D is shown projected. Similar letters refer to similar angles in the various views.



*PROJECTION or CROSS.*

**SHEET V.****Hollow Cylinders.**

This sheet introduces the use of the compasses. In one leg of the compasses insert the needle-point, and in the other leg insert the pencil, carefully sharpened.






Locate the centre lines and draw the two concentric circles to represent the top view of the cylinder at the left. Then draw the front view by projecting the side lines from the top view.

The view shown immediately to the right of these two views is known as a "sectioned" view. Imagine the cylinder cut in halves from top to bottom. The back half would present the appearance shown in the sectioned view, the "cross-hatching" or "sectioning" representing the cut surface. The sectioning is done by drawing a series of parallel lines about  $\frac{1}{8}$  inches apart. Lay the  $45^\circ$  triangle on the upper edge of the T-square and draw the topmost line of the sectioning. Then slide the triangle along the T-square for each successive line. As far as possible, draw both sides with one placing of the

triangle. The sectioning should be inked in without previous penciling and the lines should be finer than the lines of the cylinder. Various devices are in use for mechanically equalizing the distances in section-lining, but the trained eye is the most practical method. When two abutting pieces are sectioned, the section-lining on one piece slants in an opposite direction to that on the other.

The right-hand drawing is that of a hollow cylinder with a flange about the top and bottom. In practice, when an object to be sectioned is the same on both sides of its centre line, only one side is sectioned while the other side is drawn in full. This method is here shown. In the front view, the part to the left is drawn in full and that to the right is drawn in section. The top view is drawn in full, as though the front view were not sectioned.


Construction lines are omitted in inking, therefore, upon this and succeeding sheets the construction lines are not shown.

*HOLLOW CYLINDERS.*

**SHEET VI.****Mortise and Tenon Joint.**

An application of some of the foregoing principles is here made in a simple working drawing of a mortise and tenon joint. A mortise  $\frac{3}{4} \times 1\frac{1}{4}$  inches is


cut in the centre of the end piece, into which a tenon cut upon the other piece, closely fits. This is clearly shown by the drawing.

*MORTISE AND TENON JOINT.*

**SHEET VII.****Door Joint.**

A working drawing of a slightly more complicated joint is here shown. The front and side views are sufficient to make the joint from, but the top view is added to make the method of constructing the joint somewhat clearer. This joint is an end mortise and tenon joint and has a rabbet cut on the inside faces.

The rabbet is shown by the section at the lower part of the drawing. The section illustrates a method commonly used for showing transverse construction. The material is supposed to be cut through at right angles to the face and the cut surface turned up until it lies in the plane of the face.

*DOOR JOINT.*

**SHEET VIII.****Development of Cube.**


By the development of the surface of an object is meant the laying out of the pattern which, when properly folded, will exactly represent the surface of the object.

A simple and easily conceived development is that of a cube. It is necessary to know the dimensions of the faces and the number of faces, six. For example, let each face be  $2\frac{1}{4}$  inches square. Draw a square to these dimensions and let it represent the front face. Immediately above and below draw the top and bottom faces, and at the left and right the side

faces, and adjoining either side, add the back face. Such a drawing is here shown. If cut out and folded along the lines connecting the squares, the result would be a  $2\frac{1}{4}$ -inch cube.

An aid to a clearer comprehension of the principles involved in laying out patterns, and also a check to the accurateness of the work, may be obtained by duplicating this and the succeeding five patterns upon a sheet of thin card-board or stiff paper and folding to the desired shape. A lap, for pasting, should be added along outer edges.



*DEVELOPMENT of CUBE*




**SHEET IX.****Development of Square Pyramid.**

Draw the top and front views of a pyramid having a base 2 inches square and an altitude of 4 inches, and develop its surface.

To obtain the development of the surface of the pyramid it will be necessary first to carefully study the two views. These show that the pyramid has four sides and a base, and that the sides are equal triangles successively joined together. All that is required, then, is to draw four equal triangles joined together about their vertices, and upon one of the triangles to join the square base. As two sides of the triangles are equal and meet in a point, they may be considered in the pattern as radii of an arc of a circle. The next step is to find the length of this radius. A top view of one of the sides of the face triangles is shown at *A B*, and a front view of the same line is shown at *C D*. But this front view of the line is foreshortened, and it is required to find its

true length. Imagine the pyramid rotated about its axis so that the line *A B* would assume the position *A E*. Then the projection of this line in the front view is *C F*, which is the required true length. This exemplifies an important rule for developments, that the true length of each line must be ascertained, and also that the projection of the true length of a line will show as a horizontal line in a top view.

Having now found the true length of a side, *C F*, this length is taken in the compasses and an arc of indefinite length is described. From some point in this arc as a centre, and with a radius equal to a side of the base, an arc is drawn cutting the first arc. The two points are joined by a chord which represents the base of one of the triangles. This base line is laid off four times and the various points joined to the centre of the arc. Upon one of the chords a 2-inch square is drawn, completing the pattern.

*DEVELOPMENT of SQUARE PYRAMID.*

## SHEET X.


## Development of Truncated Hexagonal Prism.

Draw the top and front views of a hexagonal prism, each face of the hexagon being  $1\frac{1}{2}$  inches, and at  $2\frac{1}{2}$  inches from the base, measuring along the left-hand edge, pass a cutting plane making an angle of  $45^\circ$  with the base. Also develop the entire surface of the truncated prism thus formed.

As the sides of the hexagon are equal, their development is a line six times  $1\frac{1}{2}$  inches long. Therefore, draw a line  $6\frac{1}{2}$  inches long as the base line of the pattern, and for convenience in projecting, let it be in the prolongation of the base line of the prism. Divide this line into six equal parts, and at the points of division erect perpendiculars. On these lines cut off distances equal to the cut edges of the prism. This may be done directly by projection from the front view. Connect the tops of lines, and attach a regular hexagon to one of the sides. In order to find the true shape of the top it will be necessary to make a view at right angles to it in the front view. At right angles to the cut face draw a line, and at some point in it draw another line at right angles to

it. This latter line is shown at C D. From C and E in the front view project lines at right angles to the cut, through C and E, E in the oblique view. As the point C is on the centre line in the top view, it will also be on the centre line in the oblique view. On the line projected from E in the front view, the positions of E, E must be determined. As the line C D is only another position of the line C B, the distances of E, E from C D and C B must be the same in both instances. The positions of these points being determined, together with that of C, the remaining points are obtained in a like manner and joined in their regular order.

It now only remains to transfer this true shape of the cut surface to the rest of the pattern. Select any side as a connecting side. Then, as any point is determined by its distance from any two other points, each of the corners may be located by two intersecting arcs, the radii of which are equal to the distances from any two points previously found.

*DEVELOPMENT OF TRUNCATED HEX. PRISM.*





**SHEET XI.****Development of Cylinder.**

Draw the top and front views of a cylinder to the dimensions given, and develop the side and top surfaces.

As the circumference of a circle is 3.1416 times the diameter, the development of the side of the cylinder would be a rectangle 3.1416 times 2 inches long and 4 inches wide. The customary practice, however, is to divide the top view into a number of equal parts and step off with the dividers the same number of equal parts for the development. In the drawing, one-half of the top view is shown divided into twelve equal parts, therefore twenty-four of the parts are laid off along the base line of the pattern. The divisions of the top view are projected along the front view as elements of the cylinder, and these elements are reproduced on the pattern when it is desired to show the development of a cut. A supposed cut is here shown in the front view by a

construction line, and its development is shown on the pattern. Imagine the elements of the cylinder numbered from left to right and the elements of the pattern correspondingly numbered. Then, with the T-square, project the intersection of the first element of the cylinder with the cut, across to the first element of the pattern. The intersection of the second element with the cut is next projected to the second element of the pattern, and so on till the centre element of the pattern is reached. As the cut is the same at the back of the cylinder as in front, the right-hand side of the developed curve will be identical with the part already found, only reversed. Draw the curve in free-hand with pencil, and ink with the aid of the scroll.

The true shape of the face of the cut is an ellipse, and may be found by the method shown in the previous sheet, for finding an oblique view.

*DEVELOPMENT OF CYLINDER.*


**SHEET XII.****Development of Cone.**

Draw the top and front views of a cone having a 2-inch base and an altitude of 4 inches, and develop its surface.

As in the case of the cylinder, divide the circumference in the top view into a number of equal parts and project these divisions upon the base line of the front view. Connect these projected points with the apex of the cone. To the right of the cone describe an arc, having a side of the cone as radius and the apex as centre. On this arc lay off the development of the circumference in the top view by stepping off the same number of equal parts as there are divisions of the circumference. Connect each of the points stepped off with the apex. By drawing a circle equal to that of the top view, tangent to the arc, the pattern of the cone is completed.

If it is required to obtain the development of the frustum of a cone, the cut may be developed in the manner shown in the drawing. From the points of intersection of the cut with the various elements of the cone draw lines parallel to the base, cutting a side line. The true lengths of the cut elements are thus obtained. With the apex as centre, and with radii equal to the distances to each of the points found on the side line of the cone, describe arcs cutting the elements of the developed cone. The process is identical with that used in developing the cut of the cylinder, excepting that the points are projected by concentric arcs in the case of the cone and by parallel lines in the case of the cylinder. As in the previous sheet, the true shape of the cut face is an ellipse, and may be found by the method there indicated.



*DEVELOPMENT OF CONE*

## SHEET XIII.

## Development of Four-Piece Elbow.

Draw the top and front views of a four-piece elbow, together with its development.


The ellipses in the top view are obtained by projecting the points of intersection of the joints in the front view with the elements, to corresponding elements in the top view. Five such points are shown at G, H, G, P and J. The top view is not required in obtaining the development, and is given only as an additional exercise in drawing. First draw a 2-inch cylinder of indefinite height. At  $1\frac{1}{4}$  inches above the base draw a horizontal line D C, extending it to the right, one inch beyond the cylinder, and erect the perpendicular, C F. With the  $30^{\circ}$ - $60^{\circ}$  triangle divide the right angle thus formed into three equal angles. The sides of these angles serve as centre lines for the various parts of the elbow, and their bisectors, H J, K L, M N, are the joints. The angles may be bisected by stepping off two equal divisions on the quadrant serving as the centre line of the elbow. The joint M N, crossing the cylinder as first

drawn, completes the lowest part of the elbow. To obtain the second part, draw lines from the extremities of M N, at right angles to E C, until cut by the second joint K L. The remaining parts are obtained by the same method.

The development of the lowest part is obtained as shown in **Sheet XI**. The two central parts are alike, therefore one pattern will suffice. Draw a horizontal line E C, corresponding to the centre line E C, in the front view. Cut off distances above and below the centre line of the pattern equal to the distances above and below E C in the front view: *e.g.*, L N and K M. Connect the points found by a smooth curve. The upper part is obtained by stepping off the distances from corresponding elements of the upper part in the front view. Similar letters refer to similar points in each of the views.

The distance that the point C is from the elbow determines the curvature of the elbow; the nearer the point, the sharper the turn.

# DEVELOPMENT of FOUR-PIECE ELBOW.



## SCREW THREADS.

In the figure opposite, let A B C D represent a cylinder, and let the base line, D D, of the triangle be equal to the circumference of the cylinder. Imagine the side B D of the triangle placed against the element B D of the cylinder, and the triangle wrapped around the cylinder. The hypotenuse of the triangle would then present the appearance shown by the curve. Such a curve is called a *helix*, and the perpendicular distance between the ends of the curve is known as its *pitch*.

Another way of imagining a helix to be traced is by a point rotating about a centre and at the same time advancing in a straight line. This is clearly shown on a screw-cutting lathe in which the metal to be cut revolves with a uniform velocity and the tool is fed along a straight line parallel to the axis of the screw.

It is customary to speak of pitch as the number of threads per inch rather than by the true pitch measurement. A thread of one-eighth-inch pitch is known as "8-pitch"; that is, there are eight threads to the inch.

The following table is one that draughtsmen should be familiar with:


SELLERS' OR U. S. STANDARD SCREW THREADS.

Diam.	Pitch.	Diam.	Pitch.	Diam.	Pitch.	Diam.	Pitch
$\frac{1}{8}$	20	$\frac{1}{4}$	10	$1\frac{1}{8}$	6	$2\frac{1}{2}$	4
$\frac{3}{16}$	18	$\frac{3}{8}$	9	$1\frac{1}{4}$	$5\frac{1}{2}$	$2\frac{3}{4}$	4
$\frac{1}{2}$	16	$\frac{7}{8}$	9	$1\frac{3}{4}$	5	$2\frac{7}{8}$	$3\frac{1}{2}$
$\frac{5}{8}$	14	1	8	$1\frac{7}{8}$	5	3	$3\frac{1}{2}$
$\frac{3}{4}$	13	$1\frac{1}{8}$	7	$1\frac{7}{8}$	5	$3\frac{1}{4}$	$3\frac{1}{2}$
$\frac{7}{8}$	12	$1\frac{1}{4}$	7	2	$4\frac{1}{2}$	$3\frac{5}{8}$	$3\frac{1}{2}$
$\frac{15}{16}$	11	$1\frac{1}{2}$	7	$2\frac{1}{4}$	$4\frac{1}{2}$	$3\frac{3}{4}$	$3\frac{1}{2}$
$1\frac{1}{8}$	11	$1\frac{3}{4}$	6	$2\frac{3}{8}$	$4\frac{1}{2}$	$3\frac{7}{8}$	3
$1\frac{1}{4}$	10	$1\frac{7}{8}$	6	$2\frac{7}{8}$	4	4	3

The standard thread in the United States is known as the Sellers' thread. The angle of this thread is 60 degrees. One-eighth of the top of the thread is taken off and an equal amount added to the bottom, thus doing away with the sharp corners. A section of the Sellers' thread is shown in **Sheet XIV**, and also a section of a square thread.

Screw Threads.

HELIX AND PITCH.



## SHEET XIV.

## Screw Threads.

At the upper left-hand corner of the sheet is shown the method of obtaining the curve of a screw thread. Divide one-half the circle into any number of equal parts and divide one-half the pitch A H into the same number of equal parts, say six. Then project the points of division of the circle successively to the lines of division of the pitch, as A to A, B to B, C to C, etc. Connect the last series of points by a smooth curve. The root curve is obtained in a similar manner from the points of division on the inner circle. Observe that in a single-threaded screw the point on one side is directly opposite the root on the other.


To draw the square-threaded screw, shown in the centre drawing, lay off the pitch along the sides and sketch in lightly the squares representing the depth and width. The curves are obtained as in the case of the V-thread. Notice that part of the curves are hidden, and draw only such parts as appear in the front view.

The method of representing screw threads just explained is not used in working drawings, because of the amount of time and trouble it necessitates, and because the object of the drawing can be attained as well by a much simpler method.

Various kinds of conventionalized threads for small screws are shown at the lower part of the sheet. That shown at the left is a common method. The longer lines represent the tops of the threads and are drawn about one-eighth of an inch apart, regardless of what the pitch may be. The shorter lines are drawn slightly heavier and not quite to the sides of the thread.

At the top of the sheet straight lines are substituted for the curves of the V-thread, and at the right the thread is given a more finished appearance. In the centre of the sheet are shown two methods for drawing conventional square threads.

## SCREW THREADS.






**SHEET XV.****Springs.**

This sheet shows conventional methods of representing springs. The spring at the left may be considered as a square-threaded screw from which the body has been removed. The curves, except at the ends, are shown as straight lines.

The two springs at the right are of round wire, sections of which are shown. Draw circular arcs with centres an inch apart for the larger spring and three-eighths of an inch for the smaller one. Draw lines tangent to these arcs.



## SPRINGS.



**SHEET XVI.****Standard Bolts and Nuts.**


This sheet is designed to show the proportions of standard bolts and nuts. The diameter of the bolt is the unit from which the various proportions are derived. In the drawing, the diameter of each of the bolts is taken as one inch. The lengths of the bolts are shown as indefinite. Complete the drawing to the standard proportions for finished bolts and nuts given in the Table, page 38.

To draw the chamfer on the hexagonal nut or head, take a radius equal to the thickness of the nut and with centre at the intersection of the centre line and bottom of nut, describe an arc. The intersections of the arc with the sides of the front face determine the extremities of the two side arcs. By trial, find a point on the centre line of the side face

for an arc passing through the top of the nut and the two extremities before determined. The point is about one-quarter way down the centre line. The chamfer on the square nut is here shown as equal to that on the hexagonal nut.

A hexagonal nut may be drawn with close approximation to accuracy by the following method, which dispenses with the drawing of the hexagon: First draw the centre line of the nut, and then the top and bottom lines equal to the diameter of the bolt. Draw the front face slightly narrower than this diameter, and take the width of each of the side faces as equal to one-half the front face. Add the chamfer, as above. Three faces of a hexagonal nut should be shown, and but one face of a square nut.

## STANDARD BOLTS AND NUTS.



	ROUGH	FINISHED
$F$	$1\frac{1}{2}D + \frac{1}{8}$	$1\frac{1}{2}D + \frac{1}{16}$
$T$	$D$	$D - \frac{1}{16}$

$D$  - Outside diam of bolt.

$F$  - Short diam of head or nut

$T$  - Thickness of head or nut

$L$  - Length of bolt.

$P$  - Pitch.

$\frac{1}{P}$  - No. threads per inch.

**SHEET XVII.****Spanner Wrench. — Drop Forged.**


It is desirable that objects somewhat similar to those shown in this sheet and the sheets immediately following, be used as models. Where this is impracticable, the drawings may be used as sketches. When a drawing is to be made from the object, a pencil sketch is first made. All sketches should be free-hand and carefully executed. The dimensions are taken from the object with foot-rule and calipers.

Care should be exercised in the placing of dimensions. No general rule can be laid down, as the proper dimensioning of a drawing is a matter of experience. The draughtsman should be familiar

with machine-shop practice, and put such dimensions on his drawings as best serves the purpose of the workman.

This sheet shows a working drawing of a spanner-wrench, drop forged. All the curves are arcs of circles, the centres of which it will be necessary to locate. Draw to the dimensions given. In making working drawings, first locate the centre lines and build the drawings up about them. The figures used in dimensioning should be about one-eighth inch in height, and be strong and distinct. In inking, put in all curves first and then the straight lines.

WRENCH = DROP FORGED.




**SHEET XVIII.****Seven-inch Pulley.**

In **Sheet V** we learned that "when an object to be sectioned is the same on both sides of its centre line, only one side is sectioned, while the other side is drawn in full." In this sheet is found an application of this rule. The pulley is symmetrical about the centre of the shaft, therefore, in sectioning, one-half alone is shown. The lower half of the pulley is in outline, though the drawing would be quite as serviceable without the hidden lines.

As many dimensions as possible should be given on one view. The same dimension should not be re-

peated. Where a dimension is given on a sectioned surface, the section-lining should not cross the figures. Do not crowd the figures. Where there is not room for both the figures and the arrow-heads between the lines to be dimensioned, the arrow-heads may be placed outside the lines, as shown at the upper right-hand corner of the sheet. See that all unfinished corners of castings are rounded. Draw to the given dimensions. To show the structure of a part, a cross-section is sometimes placed on the part, as shown on one of the spokes.




**SHEET XIX.****Cone Pulley.**

When an end view of an object shows only circles, it should be omitted. Therefore, but one view of the cone pulley is necessary. The fact that an end view would show as a series of concentric circles may be expressed by placing the abbreviation "d," or "dia." after the dimensions that show diameters.

Shafts should not be sectioned. Spindles, studs, nuts, bolts and screws are also included in this rule. An application of the rule is given in the drawing, where the shaft is shown in full, while the pulley is shown in section.



**CONE PULLEY.**




**SHEET XX.****Flange Coupling**

The rule to which attention was called in the last sheet, that shafts should not be sectioned, is further emphasized in this sheet, wherein not only the shaft

is not sectioned, but also the bolt and nut. When two adjacent pieces are sectioned, the section-lining takes a different direction in each.

## FLANGE COUPLING



**SHEET XXI.****Pillow-Block.**


As a full-size drawing of the pillow-block to the dimensions given would be too large for the sheet, it becomes necessary to draw it to a reduced scale. The scale should be as large as possible; in this case, three-quarters of an inch to the inch. That is, for each inch measured upon the pillow-block, three-quarters of an inch is drawn. The dimensions should in all cases be the full dimensions of the object. Place a note upon the drawing, stating the scale to

which it is drawn when other than full scale. Centre line all holes and give the distance between centres.

An endeavor has been made to adopt a standard section-lining to represent different materials. A section-lining to represent Babbitt-metal is here shown. It consists of lines drawn at  $30^{\circ}$  or  $60^{\circ}$  in both directions. The purpose of such section-lining is generally more easily and satisfactorily obtained by giving the name of the material in a note upon the drawing.

**PILLOW BLOCK**

Goal 7-1:




**SHEET NO II.****Five-inch Clamp.**

In long screw-threading, considerable time may be saved by drawing the threads at the beginning and ending only. This practice is shown on the drawing

of the clamp. The necessity for an end view is obviated by showing in section such construction of parts as would be shown in the end view.

## 5 IN. CLAMP.



**SHEET XXIII.****Monkey Wrench.**


The pitch of the thread is here given in a note on the drawing as "Pitch-11"; it might be abbreviated to read "P-11." If the thread is a left-handed one, it is so noted on the drawing, otherwise it is understood to be right-handed. A single-thread is understood unless otherwise noted.

A scheme for putting in small dimensions is shown

in the case of the topmost dimension on the sheet. Two arrow-heads embrace the part to be dimensioned and the shaft of one of the arrows serves as the division-line of the fraction. The interior construction of the handle is here suggested, but not dimensioned. The cross-hatching indicates the knurling of the head of the bolt.



## MONKEY WRENCH.




**SHEET XXIV.****Globe Valve.**

The valve is symmetrical about its centre-line, excepting the construction of the valve seat. One-half is in section and the left-hand side of the valve is shown by hidden lines. Another method of showing

the valve seat is to break away a piece of the wall and show the entire valve seat in section. To avoid crowding, some of the minor dimensions are omitted in the drawing.

## GLOBE VALVE





## NOTES ON WORKING DRAWINGS.

**GENERAL DIRECTIONS.**

PRACTICE in the various draughting rooms may differ in details, yet is uniform in principles. These principles we have been studying in the previous sheets of this course, and are about to apply them in making a complete set of working drawings of a bench lathe. For the sake of compactness, and the arranging of a series best adapted for students' use, the set is made up of five sheets, the first of which is an assembly drawing, that is, a drawing showing the assembling of all the parts into the complete machine, and the remaining four being each a detail sheet of the four parts of the lathe, head-stock, tool-rest, tail-stock, and bed.

Other arrangements of sheets might advantageously be made; *e. g.*, all work for the forge-shop might be grouped together, and

also all work for the pattern-maker. In fact, it is the custom in some draughting rooms to make separate drawings for the machinist, the pattern-maker, and the blacksmith. Or all work required to be done on a certain machine, as a screw-cutting lathe, may be brought together.

For convenience in reference, the various points to which attention has been called in the sheets immediately preceding are here brought together under appropriate headings, and such notes are added as may be required for a comprehensive knowledge of prevailing draughting-room practice.

**I. SIZE OF SHEETS.** Some system of uniform sizes of sheets is generally adopted in draughting-offices to facilitate handling and filing. A convenient system permits of

a smaller sheet being made by halving the next larger. Such a scheme has been followed in this series. The paper comes in sheets, 22 x 30. Each sheet is cut into two sheets of 15 x 22, for large drawings, and again divided into sheets of 15 x 11 for the smaller drawings. The lathe drawings are made upon the larger sheets. The border-lines inclose a "sight" of  $19\frac{1}{2} \times 13$ . Trim to  $\frac{1}{4}$  of an inch at the top, bottom and right-hand sides. A wider margin at the left permits of binding together the series of drawings.

2. TITLE, INDEX, ETC. Leave a space of 4 x 2 in the lower right-hand corner for title, etc. A method for titles is shown on the sheets. It consists of five parts:

*a*—Name of Machine.

*b*—Detail.

*c*—Scale.

*d*—Date and Draughtsman.

*e*—Index of Drawing.

The letter of the Index should, if possible, bear some relation to the machine designated, *e. g.*, L-Lathe. The first number is used to distinguish between various types of similar machines. The final number is the particular mark of the machine bearing it. In a complete set of drawings the assembly drawing should be indexed as number one, and should contain a list of the other drawings with their numbers.

The heights of the letters in "*a*" and "*b*" are  $\frac{3}{8}$  inches for capitals and  $\frac{1}{8}$  inch for lower-case letters. Other letters and figures are  $\frac{1}{8}$  inch in height, excepting the index. Index letters and figures, *e. g.*, L-2-1 are  $\frac{3}{8}$  inches high.

The firm's name should appear somewhere on each drawing. A common usage is to put this on with a stamp which sometimes includes the date.

3. SKETCHES. Sketches should be made with care and be of such a nature that a

correct drawing or even the thing itself could be made from them by another, if necessity demanded it. A pad of manila paper, about 8x12, will be found handy for making sketches. The work should be free-hand.

4. LAYING OUT WORK. Large sheets requiring considerable time may be stretched; otherwise use tacks.

Select such views as will best show the object and as few as will show it clearly.

Find approximately the space each view will occupy and locate centre-lines.

Build up each part about its centre-lines, not completing each view separately, but projecting lines from one view to another.

5. RELATION OF VIEWS. Where more than one view is required, place the top view above the front view, the right view to the right, and the left view to the left. When an end view shows only circles, this

view should be omitted, and the letter "d," or "dia." be used in dimensioning.

6. SECTIONING. When it is desirable to show in detail the internal structure, sectioning should be used.

When an object is symmetrical about its axis, section but one-half.

Do not section bolts, nuts, screws, studs, spindles, and shafts.

The part of an object back of a sectioned view need not be shown.

Two adjacent cut surfaces should be sectioned-lined in opposite directions.

More than two cut surfaces may be distinguished by varying the width of the section-lining, or its slant.

7. INKING. If original drawings are to be inked, use black ink only. It is sufficient, however, to have the original drawing in pencil, as a tracing can be made directly from it.

Show centre-lines by light dashes, alternately  $\frac{1}{2}$  and  $\frac{1}{8}$  inches in length.

Show invisible parts by hidden lines made up of dashes about  $\frac{3}{8}$  inches long.

Construction lines should not be inked.

Ink all curved lines first; then the straight lines.

When lines radiate from a point, stop them before reaching the point, to avoid blotting.

Keep the pens sharpened.

8. DIMENSIONING. Put in dimensions after the drawing proper is completed.

All dimension figures to be, at least, a scant eighth-inch, and made to read, in horizontal dimensions from the bottom of the sheet, and in vertical dimensions from the right of the sheet.

The division line of fractions should have the same direction as dimension lines.

See that the arrow-heads rest against the lines dimensioned.

Do not use centre-lines for dimension lines.

Give dimensions in inches and fractions of an inch up to 24 inches. Above 24 inches use feet and inches, always indicating feet and inches, separated by a hyphen, thus: 5'-0", which reads five feet, no inches.

When the dimensions are in even feet, the inches should always be expressed by 0".

Give each dimension once only, regardless of the number of views.

Give dimensions over-all, that is, give the dimension of the whole in addition to the dimension of the parts.

As far as possible confine dimensions to the one view.

Designate a radius by "r" or "rad." and indicate the centre by a small circle.

The full dimensions should be given regardless of the scale of the drawing.

Dimensions should be placed upon the object, but where this would lead to crowding, the dimension may be placed adjacent to the object and connected by dashes.

Give distances between centres of bolt holes.



9. **TRACINGS.** Centre and dimension lines on tracings may be represented by full red-ink lines. The arrow-heads should be black.

Washes or crayon used for sectioning should be placed on the reverse side of the cloth.

If the ink does not readily adhere to the cloth, the surface may be brushed with chalk or talc.

10. **GENERAL NOTES.** Use explanatory notes freely.

"Finish" may be indicated by an "f," the cross-bar of the f being on the line to be finished. Or "finish" may be indicated by drawing a line in red ink adjacent to the surface to be finished.

The name of each piece and the number required for each complete machine should be marked directly over the piece.

In long screw-threading show only the beginning and ending of the thread.

A long object having the same construction throughout a considerable distance may be drawn with its central part broken out.

Do not use the scale as a ruler.

### **BLUE-PRINTING.**

It is in the form of blue-prints that the drawings generally reach the shops. The prints are made by exposing chemically prepared paper to the action of the sunlight, and then washing in water.

Prepared paper may be purchased from dealers in draughtsmen's supplies, or it may be easily made as wanted. The chemicals required for sensitizing the paper are Citrate of Iron and Ammonia, and Red Prussiate of Potash. These may be purchased at any drug-store and should not cost more than ten cents an ounce.

For making enough blue-print paper for the set of drawings of the lathe, dissolve about one ounce of Citrate of Iron and Ammonia in

four ounces of water, and about three-quarter ounces of Red Prussiate of Potash in four ounces of water. The Prussiate of Potash will dissolve more readily if it is first pounded into a powder. The relative amounts of the chemicals used vary in practice, equal quantities of each being sometimes used. The quantities given above have been found by experience to yield a deep blue color. After the chemicals are dissolved they are mixed together, and the mixture is spread upon the surface of a good, white paper. A soft paste-brush, about four inches wide, will be found serviceable for this purpose. Apply the solution evenly over the entire surface, and tack the sheet up in a dark place to dry. The paper is now sensitive to the action of light, from which it should be carefully guarded. The drying requires about an hour. The paper may be kept for some time without deterioration.

In offices where blue-printing is done, special printing frames are provided. These

consist of a board upon which two or three thicknesses of flannel or other soft cloth is smoothly fastened, over which is hinged a sheet of heavy glass. The cloth furnishes a smooth, yielding surface upon which to place the paper and tracings, and the heavy glass presses them evenly together while permitting the sunlight to act. The prepared paper is placed upon the cloth, sensitized face up, and the tracing is placed over it. They are held firmly together by the glass, and exposed to the direct action of the sun's rays. The time of exposure varies with the intensity of the sunlight, but from ten to three o'clock an exposure of from five to eight minutes should be sufficient. The printing may be done without the direct action of the sun's rays, as upon a cloudy day, by extending the time of exposure to from one to two hours.

When the paper has been exposed long enough, which is shown by the yellow color changing to a bluish-gray, it is placed on a

bath of clean water, and allowed to soak for a few minutes. It is then rinsed off and hung up to dry.

If a regular printing frame is not attainable, any simple device may be used that will keep the paper and tracing firmly pressed together and not obstruct the action of the sunlight.

If, after a blue-print is made, it is desired to add anything to it, as a measurement or a line, it may be done with an ordinary pen dipped in caustic soda, which bleaches the blue, or Chinese White may be used.

The finished parts of a machine may be shown upon a blue-print by drawing lines with red ink adjacent to such parts.

**SHEET XXV.****Bench Lathe — Assembly Drawing.**

The assembly drawing, although numbered one, is the last to be drawn in the series. It is made directly from the detail sketches. The numbers upon the assembly drawing refer to the numbers of the various parts and show how they are assembled.

For example, the head-stock frame in the assembly drawing is marked "2-1." By looking at the "List of Drawings" given in the lower left-hand corner of the sheet, it will be seen that "2" is the number of the sheet containing the details of the head-stock, and that the number of the frame is "1" on that sheet. Again, the hand-wheel on the tail-stock is numbered "4-6," which means, detail number 6 on sheet number 4.

As a rule, it is better not to shade a drawing. There are places where shade-lining tends to bring out more clearly the meaning of a drawing, but such cases are the exception. This sheet would be quite as serviceable without the shade lines. It adds somewhat of a finish to the drawing, but is here given simply as an example, and to explain the method. The light is supposed to come from the upper left-hand corner of the sheet at an angle of  $45^{\circ}$ . Therefore, the bottom and right-hand lines are made heavier. The thickness of the shade line should be upon the outside of the line.

Sometimes the principal over-all dimensions are shown on the assembly drawing.

Bench Lathe  
Assembly.  
SCALE - HALF SIZE.  
4-8-96. O. DEL.

**L-2-I**


**SHEET XXVI.****Bench Lathe — Details of Head-Stock.**

The designing of a machine and the making of the original drawings for it is not a subject to concern the student of elementary mechanical drawing. That is the work of the experienced designer and draughtsman. The best practice for the student is to make drawings of some machine already built.

Suppose the bench lathe under consideration to be such a machine. The first thing to do is to take the machine apart and make careful free-hand sketches of each part, fully dimensioning. Section-paper, a paper lightly lined to inches and fractions of an inch, will be

found of assistance in making correctly proportioned sketches. From these sketches the mechanical drawing is made in pencil. As every one cannot have a machine to take apart and make sketches of, the student may consider these sheets as sketches and make his drawings directly from them, working to the given dimensions.

Each detail on this sheet should be carefully studied and the reason for each line and dimension should, with the aid of the preceding explanations, be understood.




**SHEET XXVII.****Bench Lathe—Details of Tool Rest.**

But two views of the post are necessary to give all the dimensions; the bottom view shows a little more clearly the shape of that part of the post. The tap (internal screw-threading) on the post is shown by parallel hidden lines in the side view and by the note, " $\frac{3}{8}$  in. tap." The tap is shown in the front view

by two circles. This method is also shown on the clamping lever. Where a definite pitch is not given of screw threads, as in the case of the fastening bolt, it is understood to be standard. The bolt is five-eighths inches in diameter, therefore the pitch of the screw-threading is eleven. (See Table on page 38.)





## SHEET XXVIII.

## Bench Lathe—Details of Tail Stock.

But one view of the nuts is shown, and in each case the height alone is given. This would indicate that the nuts are standard, and the height of the nut equals the diameter of the bolt. Therefore, the taps of the stud bolt nut and the hand wheel nut are

$\frac{1}{2}$ -inches and  $\frac{3}{4}$ -inches respectively. Another method of indicating a tap is given on the tail stock frame, where the thread is shown by conventional hidden lines.


The taper of the centre might have been expressed by giving the amount of rise to each inch.



**SHEET XXIX.****Bench Lathe — Details of Bed.**

This sheet is drawn to half-scale. As the structure of the bed is the same throughout a considerable length, space may be saved by breaking out a piece and showing only the ends. The dimension overall is given. The section here shown as an end view is frequently drawn in the broken-out portion as indicat-

ing the structure of the object at that part. Sometimes drawings made to different scales are placed upon the same sheet. On this sheet the bed and leg are drawn to half-scale, but the bolt might have been drawn full size, on account of its relative smallness, and a note giving its scale added.



## SHEET XXX.

**Isometric Drawing.**

Isometric drawings are relatively easy to make and understand, and in a single view give information that in an ordinary mechanical drawing would require two or more views. They have the disadvantage of appearing distorted and also of limiting measurements to three directions.




In making an isometric drawing all vertical lines, or lines representing height, as line A B, are drawn as vertical lines; all lines representing widths, as line A C, are drawn at  $30^\circ$  to the right; and all lines representing depth, as line A E, are drawn  $30^\circ$  to the left. On these three lines, and lines parallel to them, measurements may be made, but all other lines will vary from their true length. E.g. A B and A C are 3 inches long in both the front view and in the isometric view, and A E is 2 inches. But take any line outside of the isometric lines, as the distance A D; on the front view the true measurement of this distance is found to be about  $4\frac{1}{4}$  inches, whereas in the isometric view it is about  $5\frac{1}{8}$  inches.

Draw the 3-inch square shown at the bottom of the

sheet and then draw the same square in isometric projection. First draw the vertical line A B and then the lines A C and B D at  $30^\circ$  to the horizontal. Draw A E at  $30^\circ$  and fill in the remaining lines.

Inscribe a circle in the square. To make an isometric drawing of this circle first make the isometric view of the square as shown in the right-hand upper corner. Divide B D into a number of equal parts, as at F, G, H, I and J. From these points drop vertical lines and on these lines take the measurements F f, G g, etc. Carry out the same method with the other three sides of square. The result will be a series of points f, g, h, i, j, etc., through which a smooth curve should be drawn. This curve will prove to be an ellipse, which is the isometric drawing of the circle. By drawing the rear ellipse and the two connecting tangent lines an isometric drawing of a cylinder is obtained. Any curve may be drawn isometrically by the method of offsets used in making this isometric drawing of a circle.

## ISOMETRIC DRAWINGS





**SHEET XXXI.****Isometric Drawing of a Face Plate.**

As a practical example of the application of isometric drawing a face plate is shown in Sheet XXXI. Having made the isometric drawing of the circle in

Sheet XXX the student will readily comprehend the method of making this or a similar drawing.



*FACE PLATE*




**SHEET XXXII.****Isometric Sketching.**

The Norman W. Henley Publishing Company, at 2 West 45th Street, New York, has placed upon the market an isometric sketching paper \* that affords a convenient and ready means of making isometric

drawings. The isometric lines are lightly printed upon the paper and with these as a background isometric drawings may be readily made. Sheet XXXII shows the method of using the prepared paper.

\* This isometric paper is supplied in pads as follows:

Pads (40 sheets) 6 x 9 .....	40 cents
Pads (40 sheets) 9 x 12 .....	75 cents
Pads (40 sheets) 12 x 18 .....	\$1.50



**THE  
JOHN CRERAR  
LIBRARY**

## PARALLEL COURSE.



## PARALLEL COURSE EXERCISES

---

THE following exercises constitute an independent series, parallel to the regular course, and may be pursued in preference to the regular course by those who desire to avoid any tendency towards copying. Each sheet differs but slightly from the corresponding sheet of the regular course, and may readily be drawn from the directions accompanying the regular sheet.

### EXERCISE I.

**Square Prisms.** Draw the top and front views of a square prism, the base of which is 2 inches square and the height 3 inches. Show three positions as in **Sheet I.**

### EXERCISE II.

**Triangular and Hexagonal Pyramids.** A pyramid differs from a prism in that its sides meet in a point. Draw the top and front views of a triangular pyramid 4 inches in height and having each side of the base 2 inches. Also draw the top, front, and left-hand views of a hexagonal pyramid 4 inches in height, having each side of the base  $1\frac{1}{2}$  inches.

### EXERCISE III.

**Projection of a Square Prism.** Draw the front, top and two side views of a square prism, having an altitude of 4 inches, base 2 inches square, and tilted  $30^\circ$  to the right.

### EXERCISE IV.

**Projection of a Double Cross.** Add to the cross shown in **Sheet IV** another arm, at right angles to the one given, and of similar dimensions. The top view will then present a cross, the arms of which are each one inch square. Draw the various projections shown in **Sheet IV.**

### EXERCISE V.

**Sectioned Views.** Draw the top and front views, and half-section of a square prism, 4 inches high, with  $2\frac{1}{2}$ -inch base, and having a bore of  $1\frac{1}{2}$  inches in diameter.

Also draw the top and front views of a similar prism having a flange at the top and bottom  $\frac{1}{2}$  inch high and overhanging  $\frac{1}{4}$  inch. Show one-half of the front view in section.

## EXERCISES VI AND VII.

**Joints.** Make working drawings of two simple joints, as of a Lap Joint and a Sash Joint.

## EXERCISE VIII.

**Development of a Rectangular Block.** Draw the development of the surface of a rectangular block, 3 inches long, 2 inches deep, and  $2\frac{1}{2}$  inches high.

## EXERCISE IX.

**Development of a Rectangular Pyramid.** Draw the top and front views, and the development of the entire surface of a pyramid having a rectangular base  $2\frac{1}{2} \times 2$  inches, and an altitude of 4 inches.

## EXERCISE X.

**Development of a Truncated Square Pyramid.** At half the altitude of the square pyramid of **Sheet IX** make a cut at  $45^\circ$  to the base and develop the entire surface of the lower part, including the cut surface. It will be necessary to show the cut in the top view, and this may be obtained by projecting the intersections of the cut and the sides of the pyramid to these sides as shown in the top view, and by joining the points thus found. The entire drawing of **Sheet IX** should first be made, as the cut is then more readily determined.

## EXERCISE XI.

**Development of an Elliptical Cylinder.** Draw the top and front views, and the development of a cylinder having an altitude of 4 inches, and an elliptical base, the major (longer) axis of the ellipse being  $2\frac{1}{2}$  inches and the minor (shorter) axis  $1\frac{1}{2}$  inches. Cut the cylinder by an inclined plane and develop the cut. The ellipse is stepped off into a number of equal parts as in the case of the circle in **Sheet XI**.




FIG 4.

A simple method of drawing a true ellipse, when the major and minor axes are known, is shown in the diagram Fig. 4. Let  $AB$  be the major axis and  $CD$  the minor axis. On a slip of paper lay off  $EF$  equal to



one-half A B, and G F equal to one-half C D. Then keeping the point E always on the line C D and the point G always on the line A B, the point F will describe the required ellipse. Find a number of positions of the point F and through these points draw a smooth curve.

## EXERCISE XII.

**Development of an Elliptical Cone.** Draw the top and front views, and the development of a cone having an altitude of 4 inches, and an elliptical base, the major axis of the ellipse being  $2\frac{1}{4}$  inches and the minor axis  $1\frac{3}{4}$  inches. Cut the cone by an inclined plane and develop the cut.

## EXERCISE XIII.

**Development of a Five-Piece Elbow.** Draw the front view and development of a five-piece elbow of the same general dimensions as given for the four-piece elbow.

## EXERCISE XIV.

**Screw Threads.** The regular sheet on Screw Threads contains, in a compact form, much with which the student of the subject should be familiar. Any departure from the general make-up of the sheet

should, therefore, not be attempted. A slight variation of the dimension given is the only change that should be made. This will be sufficient to give a somewhat different curvature to the lines.

## EXERCISE XV.

**Springs.** Sheet XV may be varied by closing the springs until the spaces are but three-quarters of the distances given, while the other dimensions remain the same.

## EXERCISE XVI.

**Bolts and Nuts.** Substitute for the two bolts and nuts of Sheet XVI similar ones of  $1\frac{3}{4}$  inches diameter of bolt, and 7 inches in length. Lay lengthwise of the sheet and draw without the top views of the nuts, by the method given in the latter part of the explanations accompanying Sheet XVI. Give all dimensions shown by letters in Sheet XVI.

## EXERCISES XVII TO XXIV.

**Simple Working Drawings.** Make working drawings of small articles that are not complex in their character. The following list may be suggestive of suitable material:

Various kinds of pulleys, clamps, wrenches, valves, simple vises, faucets, anvils; shafting details — as couplings, pillow-blocks, and hangers; engine details — as ends, cranks, eccentrics, cross-heads and guides, etc.

## EXERCISES XXV TO XXIX.

**Working Drawings.** Make a complete set of working drawings of some small machine, like a drill-press or bench-lathe, or of a small engine.


1922  
REVISED

# CATALOGUE

*of LATEST and BEST*

## Practical and Mechanical Books

Including Automobile and Aviation Books



*PRACTICAL BOOKS FOR PRACTICAL MEN*


Any of these books will be sent prepaid to any part of the world, on receipt of price. Remit by Draft, Postal Order, Express Order or Registered Letter.

---

*Published and For Sale by*  
**The Norman W. Henley Publishing Co.**  
2 West 45th Street      New York, U. S. A.

## INDEX TO SUBJECTS

Accidents .....	27	Locomotive Engineering,	24, 25, 26, 27
Air Brake .....	25, 26	Machine Shop Practice,	27, 29, 30, 31
Arithmetic .....	15, 29, 38	Manual Training .....	32
Automobiles ....	3, 4, 5, 6, 7	Marine Engineering ...	32
Automobile Charts ....	7	Mechanical Magazine ..	28
Aviation .....	8	Mechanical Movements.	30
Batteries .....	18	Metal Turning .....	23
Bevel Gears .....	22	Metal Work Dies ....	13, 14
Brazing and Soldering.	9	Mining .....	33
Cams .....	22	Motor Cycles .....	6, 7
Charts .....	7, 8, 9	Patents and Inventions.	23
Chemistry .....	21	Pattern Making .....	33
Civil Engineering ....	29	Perfumery .....	34
Coke .....	10	Plumbing .....	34
Compressed Air .....	10	Receipt Book .....	35, 40
Concrete .....	10, 11, 12, 13	Refrigeration and Ice..	22
Cosmetics .....	34	Repairing Automobiles..	6
Dictionaries .....	14	Rubber .....	36
Dies—Metal Work ...	13, 14	Saws .....	36
Drawing—Sketching		Screw Cutting .....	36
Paper .....	14, 15	Sheet Metal Work ...	13, 14
Electric Bells .....	16	Smoke Prevention ....	20
Electricity..	15, 16, 17, 18, 19	Soldering .....	9
Encyclopedia .....	29	Starting Systems .....	5
Factory Management,		Steam Engineering..	36, 37, 38
etc. ....	19	Steam Heating and Ven-	
Ford Automobile .....	6	tilation .....	38
Fuel .....	20	Steel .....	38, 39
Flying Machines .....	8	Storage Batteries .....	18
Gas Engines and Gas,		Switch Boards .....	17, 19
20, 21, 22		Tractor .....	22, 39
Gearing and Cams ....	22	Turbines .....	39
Hydraulics .....	22	Ventilation .....	38
Ice and Refrigeration..	22	Waterproofing .....	13
Inventions—Patents ...	23	Welding .....	5
Knots .....	23	Wiring .....	17, 18
Lathe Work .....	23, 24	Wireless Telephones ..	19
Link Motion .....	25		
Liquid Air .....	24		

 Any of these books will be sent prepaid to any part of the world, on receipt of price.

REMIT by Draft, Postal Money Order, Express Money Order, or by Registered Mail.

## GOOD, USEFUL BOOKS

### AUTOMOBILES—MOTORCYCLES

#### **The Modern Gasoline Automobile, Its Design, Construction, Operation.**

By VICTOR W. PAGE, M.S.A.E. This is the most complete, practical, and up-to-date treatise on gasoline automobiles and their component parts ever published. In the new revised and enlarged 1920 edition, all phases of automobile construction, operation and maintenance are fully and completely described and in language anyone can understand. Every part of all types of automobiles, from light cyclecars to heavy motor trucks and tractors, are described in a thorough manner; not only the automobile, but every item of its equipment, accessories, tools needed, supplies and spare parts necessary for its upkeep, are fully discussed. It is clearly and concisely written by an expert familiar with every branch of the automobile industry and the originator of the practical system of self-education on technical subjects; it is a liberal education in the automobile art, useful to all who motor for either business or pleasure. Anyone reading the incomparable treatise is in touch with all improvements that have been made in motor car construction. All latest developments, such as high speed aluminum motors and multiple valve and sleeve valve engines, are considered in detail. The latest ignition, carburetor and lubrication practice is outlined. New forms of change speed gears, and final power transmission systems, and all latest chassis improvements, are shown and described. This book is used as a text in all leading automobile schools, and is conceded to be the standard treatise. The chapter on Starting and Lighting Systems has been greatly enlarged, and many automobile engineering features that have long puzzled laymen are explained so clearly that the underlying principles can be understood by anyone. This book was first published six years ago, and so much new matter has been added to the book that it is nearly twice its original size. The only treatise covering various forms of war automobiles and recent developments in motor truck design, as well as pleasure cars. This book is not too technical for the layman nor too elementary for the more expert. It is an incomparable work of reference for home or school. 6 x 9. Cloth, 1,000 pages, nearly 1,000 illustrations, 12 folding plates.

**Price, \$4.00**

#### **Questions and Answers Relating to Modern Automobile Construction, Driving and Repair.**

By VICTOR W. PAGE. A self-educator on automobiling without an equal. This practical treatise consists of a series of thirty-seven lessons, covering with over 2,000 questions and their answers—the automobile, its construction, operation and repair. The subject matter is absolutely correct and explained in simple language. If you can't answer all of the following questions, you need this work. The answers to these and 2,000 more are to be found in its pages.

Give the name of all important parts of an automobile and describe their functions. Describe action of latest types of kerosene carburetors. What is the difference between a "double" ignition system and a "dual" ignition system? Name parts of an induction coil. How are valves timed? What is an electric motor starter and how does it work? What are advantages of worm drive gearing? Name all important types of ball and roller bearings. What is a "three-quarter" floating axle? What is a two-speed axle? What is the Vulcan electric gear shift? Name the causes of lost power in automobiles. Describe all noises due to deranged mechanism and give causes. How can you adjust a carburetor by the color of the exhaust gases? What causes "popping" in the carburetor? What tools and supplies are needed to equip a car? How do you drive various makes of cars? What is a differential lock and where is it used? Name different systems of wire wheel construction. What is a "positive" drive differential? etc., etc. Answers every question asked relating to the modern automobile. A popular work at a popular price. 5¼ x 7¼. Cloth. 650 pages, 392 illustrations, 3 folding plates. 1920 Edition just published.

**Price, \$2.50**

#### **How to Run an Automobile.**

By VICTOR W. PAGE. This treatise gives concise instructions for starting and running all makes of gasoline automobiles, how to care for them, and gives distinctive features of control. Describes every step for shifting gears, controlling engine, etc. Among the chapters contained are: I. Automobile Parts and Their Functions. II. General Starting and Driving Instructions. III. Typical 1919 Control Systems—Care of Automobiles. Thoroughly illustrated. 178 pages, 72 illustrations.

**Price, \$1.50**

#### **The Automobilist's Pocket Companion and Expense Record.**

By VICTOR W. PAGE. This book is not only valuable as a convenient cost record, but contains much information of value to motorists. Includes a condensed digest of auto laws of all States, a lubrication schedule, hints for care of storage battery and care of tires, location of road troubles, anti-freezing solutions, horsepower table, driving hints and many useful tables and recipes of interest to all motorists. Not a technical book in any sense of the word, just a collection of practical facts in simple language for the everyday motorist. Convenient pocket size.

**Price, \$1.25**

## Gasoline and Kerosene Carburetors, Construction, Installation and Adjustment.

By CAPT. V. W. PAGÉ. All leading types of carburetors are described in detail, special attention being given to the forms devised to use the cheaper fuels such as kerosene. Carburetion troubles, fuel system troubles, carburetor repairs and installation, electric primers and economizers, hot spot manifolds and all modern carburetor developments are considered in a thorough manner. Methods of adjusting all types of carburetors are fully discussed as well as suggestions for securing maximum fuel economy and obtaining highest engine power. 250 pages, 89 illustrations. **Price, \$2.00**

## Starting, Lighting and Ignition Systems.

By VICTOR W. PAGÉ. A practical treatise on latest automobile starting, lighting and ignition system practice. This practical volume has been written with special reference to the requirements of the reader desiring easily understood explanatory matter relating to all types of automobile electrical systems. It can be understood by anyone, even without electrical knowledge, because elementary electrical principles are considered before any attempt is made to discuss features of the various systems. These basic principles are clearly stated and illustrated with simple diagrams. All the leading systems of starting, lighting and ignition have been described and illustrated with the cooperation of the experts employed by the manufacturers. Over 200 wiring diagrams are shown in both technical and nontechnical forms. Complete data is given for locating troubles in all systems, the various steps being considered in a logical way for those without expert electrical knowledge. All ignition systems receive full consideration, starting with the simplest battery and coil forms found on early cars to the modern short-contact timer and magneto methods used with the latest eight and twelve-cylinder motors. Full directions are given for making all repairs and complete instructions for locating troubles with meters. This book is unusually complete, as it also includes descriptions of various accessories operated by electric current, such as electrical gear shifts, brake actuation, signaling devices, vulcanizers, etc. Over 700 pages, 425 specially made engravings. 1920 Edition, Revised and Enlarged. **Price, \$3.00**

## Automobile Welding with the Oxy-Acetylene Flame.

By M. KEITH DUNHAM. Explains in a simple manner apparatus to be used, its care, and how to construct necessary shop equipment. Proceeds then to the actual welding of all automobile parts, in a manner understandable by everyone. *Gives principles never to be forgotten.* This book is of utmost value, since the perplexing problems arising when metal is heated to a melting point are fully explained and the proper methods to overcome them shown. 167 pages, fully illustrated. **Price, \$1.50**

## Automobile Repairing Made Easy.

By VICTOR W. PAGÉ. A thoroughly practical book containing complete directions for making repairs to all parts of the motor car mechanism. Written in a thorough but nontechnical manner. Gives plans for workshop construction, suggestions for equipment, power needed, machinery and tools necessary to carry on business successfully. Tells how to overhaul and repair all parts of all automobiles. The information given is founded on practical experience, everything is explained so simply that motorists and students can acquire a full working knowledge of automobile repairing. Other works dealing with repairing cover only certain parts of the car—this work starts with the engine, then considers carburetion, ignition, cooling and lubrication systems. The clutch, change speed gearing and transmission system are considered in detail. Contains instructions for repairing all types of axles, steering gears and other chassis parts. Many tables, short cuts in figuring and rules of practice are given for the mechanic. Explains fully valve and magneto timing, "tuning" engines, systematic location of trouble, repair of ball and roller bearing, shop kinks, first aid to injured and a multitude of subjects of interest to all in the garage and repair business. All illustrations are especially made for this book, and are actual photographs or reproductions of engineering drawings. This book also contains Special Instructions on Electric Starting, Lighting and Ignition Systems, Tire Repairing and Rebuilding, Autogenous Welding, Brazing and Soldering, Heat Treatment of Steel, Latest Timing Practice, Eight and Twelve-Cylinder Motors, etc., etc. You will never "Get Stuck" on a Job if you own this book. 1,000 specially made engravings on 500 plates, 1,056 pages (5½ x 8). 1920 Edition. **Price, \$4.00**

## The Model T Ford Car, Its Construction, Operation and Repair, Including the Fordson Farm Tractor, F. A. Lighting and Starting System, Ford Motor Truck.

By VICTOR W. PAGÉ. This is the most complete and practical instruction book ever published on the Ford car and Fordson tractor. A high grade, cloth bound book, printed on the best paper, illustrated by specially made drawings and photographs. All parts of the Ford Model T car and Fordson tractor are described and illustrated in a comprehensive manner. The construction is fully treated and operating principle made clear to everyone. Complete instructions for driving and repairing are given. To the 1920 Revised Edition matter has been added on the Ford Truck and Tractor Conversion Sets and Genuine Fordson Tractor. All parts are described. All repair processes illustrated and fully explained. Written so all can understand—no theory, no guesswork. New Edition. 153 illustrations, 410 pages, 2 large folding plates. **Price, \$2.00**

## Motorcycles, Side Cars and Cyclecars, Their Construction, Management and Repair.

By VICTOR W. PAGÉ. Describes fully all leading types of machines, their design, construction, maintenance, operation and repair. 550 pages, 350 specially made illustrations, 5 folding plates. New Edition. **Price, \$2.50**

# Automobile Charts

By VICTOR W. PAGÉ, M.S.A.E.

THE POPULAR AUTOMOBILE SERIES  
UNIFORM SIZE—24" x 38"—PRICE 35 CENTS EACH

## Location of Gasoline Engine Troubles Made Easy.

This chart shows clearly all parts of a typical four-cylinder gasoline engine of the four-cycle type. It simplifies location of all engine troubles. No details omitted. Price, 35 cents

## Location of Carburetion Troubles Made Easy.

It shows clearly how to find carburetion troubles and names all defects liable to exist in the various parts. Instructions are given for carburetor adjustment. Price, 35 cents.

## Location of Ignition System Troubles Made Easy.

In this chart all parts of a typical double ignition system using battery and magneto current are shown, and suggestions are given for readily finding ignition troubles and eliminating them when found. Price, 35 cents

## Location of Cooling and Lubricating Troubles.

This is a combination chart showing all components of the approved form of water cooling group as well as a modern engine lubrication system. It shows all points where defects exist that may result in engine overheating, both in cooling and oiling systems. Price, 35 cents

## Lubrication of the Motor Car Chassis.

This chart presents the plan view of a typical six-cylinder chassis of standard design and outlines all important bearing points requiring lubrication, and is a valuable guide to the correct lubrication of any modern car. A practical chart for all interested in motor car maintenance. Price, 35 cents

*While each chart is complete in itself, the set covers all maintenance instructions for the entire automobile. Sold singly. Securely wrapped.*

## Location of Starting and Lighting System Faults.

The most complete chart yet devised, showing all parts of the modern automobile starting, lighting and ignition systems, giving instructions for systematic location of all faults in wiring, lamps, motor or generator, switches and all other units. Invaluable to motorists, chauffeurs and repairmen. Size 24 x 38 inches. Price, 35 cents

## Location of Ford Engine Troubles Made Easy.

Chart showing clear sectional views depicting all portions of the Ford power plant and auxiliary groups. It outlines clearly all parts of the engine, fuel supply systems, ignition group and cooling system, that are apt to give trouble, detailing all derangements that are liable to make an engine lose power, start hard, or work irregularly. This chart simplifies location of all engine faults. Size 25 x 38 inches. Price, 35 cents

## Location of Motorcycle Troubles Made Easy.

This chart simplifies location of all power-plant troubles and will prove of value to all who have to do with the operation, repair or sale of motorcycles. No details omitted. Size 30 x 20 inches. Price, 35 cents

## AVIATION

### A B C of Aviation.

By CAPT. V. W. PAGÉ. This book describes the basic principles of aviation, tells how a balloon or dirigible is made and why it floats in the air. Describes how an airplane flies. It shows in detail the different parts of an airplane, what they are and what they do. Describes all types of airplanes and how they differ in construction; as well as detailing the advantages and disadvantages of different types of aircraft. It includes a complete dictionary of aviation terms and clear drawings of leading airplanes. The reader will find simple instructions for unpacking, setting up and rigging airplanes. A full description of airplane control principles is given and methods of flying are discussed at length.

This Book answers every question one can ask about modern aircraft, their construction and operation. A self educator on aviation without an equal. 275 pages, 130 specially made illustrations with 7 plates. Price, \$2.50

### Aviation Engines—Design; Construction; Repair.

By LIEUT. VICTOR W. PAGÉ, Aviation Section, S.C.U.S.R. This treatise, written by a recognized authority on all of the practical aspects of internal combustion engine construction, maintenance and repair, fills the need as no other book does. The matter is logically arranged; all descriptive matter is simply expressed and copiously illustrated, so that anyone can understand airplane engine operation and repair even if without previous mechanical training. This work is invaluable for anyone desiring to become an aviator or aviation mechanic.

The latest rotary types, such as the Gnome Monosoupape, and LeRhône, are fully explained, as well as the recently developed Vee and radial types. The subjects of carburetion, ignition, cooling and lubrication also are covered in a thorough manner. The chapters on repair and maintenance are distinctive and found in no other book on this subject. Not a technical book, but a practical, easily understood work of reference for all interested in aeronautical science. 576 pages, 253 illustrations. Price, Net, \$3.00

### Glossary of Aviation Terms—English-French; French-English.

A complete glossary of practically all terms used in aviation, having lists in both French and English with equivalents in either language compiled by LIEUTS. VICTOR W. PAGÉ, A.S., S.C.U.S.R., and PAUL MONTARIOL, of the French Flying Corps. Price, Net, \$1.00

### Aviation Chart—Location of Airplane Power Plant Troubles Made Easy.

By LIEUT. VICTOR W. PAGÉ, A.S., S.C.U.S.R. A large chart outlining all parts of a typical airplane power plant, showing the points where trouble is apt to occur and suggesting remedies for the common defects. Intended especially for aviators and aviation mechanics on school and field duty. Price, 35 cents

## BRAZING AND SOLDERING

### **Brazing and Soldering.**

By JAMES F. HOBART. The only book that shows you just how to handle any job of brazing or soldering that comes along; it tells you what mixture to use, how to make a furnace if you need one. Full of valuable kinks. The fifth edition of this book has just been published, and to it much new matter and a large number of tested formulas for all kinds of solders and fluxes have been added. **Price, 35c.**

## CHARTS

### **Aviation Chart—Location of Airplane Power Plant Troubles Made Easy.**

By LIEUT. VICTOR W. PAGÉ, A.S., S.C.U.S.R. A large chart outlining all parts of a typical airplane power plant, showing the points where trouble is apt to occur and suggesting remedies for the common defects. Intended especially for aviators and aviation mechanics on school and field duty.

**Price, 35 cents**

### **Modern Submarine Chart—With 200 Parts Numbered and Named.**

A cross-section view, showing clearly and distinctly all the interior of a submarine of the latest type. No details omitted—everything is accurate and to scale. This chart is really an encyclopedia of a submarine.

**Price, 25 cents**

### **Box Car Chart.**

A chart showing the anatomy of a box car, having every part of the car numbered and its proper name given in a reference list.

**Price, 25 cents**

### **Gondola Car Chart.**

A chart showing the anatomy of a gondola car, having every part of the car numbered and its proper reference name given in a reference list.

**Price, 25 cents**

### **Passenger Car Chart.**

A chart showing the anatomy of a passenger car, having every part of the car numbered and its proper name given in a reference list.

**Price, 25 cents**

### **Steel Hopper Bottom Coal Car.**

A chart showing the anatomy of a steel hopper bottom coal car, having every part of the car numbered and its proper name given in a reference list.

**Price, 25 cents**

### **Tractive Power Chart.**

A chart whereby you can find the tractive power or drawbar pull of any locomotive without making a figure. Shows what cylinders are equal, how driving wheels and steam pressure affect the power. What sized engine you need to exert a given drawbar pull or anything you desire in this line.

**Price, 50 cents**

### **Horse-power Chart.**

Shows the horse-power of any stationary engine without calculation. No matter what the cylinder diameter of stroke, the steam pressure or cut-off, the revolutions, or whether condensing or non-condensing, it's all there. Easy to use, accurate and saves time and calculations. Especially useful to engineers and designers.

**Price, 50 cents**

### **Boiler Room Chart.**

By GEORGE L. FOWLER. A chart—size 14 x 28 inches—showing in isometric perspective the mechanisms belonging in a modern boiler room. This chart is really a dictionary of the boiler room—the names of more than 200 parts being given.

**Price, 25 cents**

## COKE

### **Coke—Modern Coking Practice, Including Analysis of Materials and Products.**

By J. E. CHRISTOPHER and T. H. BYROM. This, the standard work on the subject, has just been revised and is now issued in two volumes. It is a practical work for those engaged in Coke manufacture and the recovery of By-products. Fully illustrated with folding plates. It has been the aim of the authors, in preparing this book, to produce one which shall be of use and benefit to those who are associated with, or interested in, the modern developments of the industry. Among the chapters contained in Volume I are: Introduction; Classification of Fuels; Impurities of Coals; Coal Washing; Sampling and Valuation of Coals, etc.; Chlorific Power of Fuels; History of Coke Manufacture; Developments in Coke Oven Design; Recent Types of Coke Ovens; Mechanical Appliances at Coke Ovens; Chemical and Physical Examination of Coke. Volume II covers By-products. Each volume is fully illustrated, with folding plates.

**Price, \$3.00 per volume**

## COMPRESSED AIR

### **Compressed Air in all Its Applications.**

By GARDNER D. HISCOX. This is the most complete book on the subject of air that has ever been issued, and its thirty-five chapters include about every phase of the subject one can think of. It may be called an encyclopedia of compressed air. It is written by an expert, who, in its 665 pages, has dealt with the subject in a comprehensive manner, no phase of it being omitted. Over 500 illustrations. Fifth Edition, revised and enlarged. Cloth bound, **\$6.00**. Half Morocco, revised and enlarged. Cloth bound.

**Price, \$6.00**

## CONCRETE

### **Concrete Wall Forms.**

By A. A. HOUGHTON. A new automatic wall clamp, is illustrated with working drawings. Other types of wall forms, clamps, separators, etc., are also illustrated and explained.

**Price, 75 cents**



### **Concrete Floors and Sidewalks.**

By A. A. HOUGHTON. The molds for molding squares, hexagonal and many other styles of mosaic floor and sidewalk blocks are fully illustrated and explained. **Price, 75 cents**

### **Practical Concrete Silo Construction.**

By A. A. HOUGHTON. Complete working drawings and specifications are given for several styles of concrete silos, with illustrations of molds for monolithic and block silos. The tables, data, and information presented in this book are of the utmost value in planning and constructing all forms of concrete silos. **Price, 75 cents**

### **Molding Concrete Bath Tubs, Aquariums and Natatoriums.**

By A. A. HOUGHTON. Simple molds and instruction are given for molding different styles of concrete bath tubs, swimming pools, etc. **Price, 75 cents**

### **Molding Concrete Chimneys, Slate and Roof Tiles.**

By A. A. HOUGHTON. The manufacture of all types of concrete slate and roof tile is fully treated. Valuable data on all forms of reinforced concrete roofs are contained within its pages. The construction of concrete chimneys by block and monolithic systems is fully illustrated and described. A number of ornamental designs of chimney construction with molds are shown in this valuable treatise. **75 cents**

### **Molding and Curing Ornamental Concrete.**

By A. A. HOUGHTON. The proper proportions of cement and aggregates for various finishes, also the methods of thoroughly mixing and placing in the molds, are fully treated. An exhaustive treatise on this subject that every concrete worker will find of daily use and value. **Price, 75 cents**

### **Concrete Monuments, Mausoleums and Burial Vaults.**

By A. A. HOUGHTON. The molding of concrete monuments to imitate the most expensive cut stone is explained in this treatise, with working drawings of easily built molds. Cutting inscriptions and designs is also fully treated. **75 cents**

### **Concrete Bridges, Culverts and Sewers.**

By A. A. HOUGHTON. A number of ornamental concrete bridges with illustrations of molds are given. A collapsible center of core for bridges, culverts and sewers is fully illustrated with detailed instructions for building. **75 cents**

### **Constructing Concrete Porches.**

By A. A. HOUGHTON. A number of designs with working drawings of molds are fully explained so any one can easily construct different styles of ornamental concrete porches without the purchase of expensive molds. **Price, 75 cents**

### **Molding Concrete Flower Pots, Boxes, Jardinieres, Etc.**

By A. A. HOUGHTON. The molds for producing many original designs of flower pots, urns, flower boxes, jardinieres, etc., are fully illustrated and explained, so the worker can easily construct and operate same. **Price, 75 cents**

### **Molding Concrete Fountains and Lawn Ornaments.**

By A. A. HOUGHTON. The molding of a number of designs of lawn seats, curbing, hitching posts, pergolas, sun dials and other forms of ornamental concrete, for the ornamentation of lawns and gardens, is fully illustrated and described. **75c.**

### **Concrete on the Farm and in the Shop.**

By H. COLVIN CAMPBELL. This is a new book from cover to cover, illustrating and describing in plain, simple language many of the numerous appliances of concrete within the range of the home worker. Among the subjects treated are: Principles of reinforcing; methods of protecting concrete so as to insure proper hardening; home-made mixers; mixing by hand and machine; form construction, described and illustrated by drawings and photographs; construction of concrete walls and fences; concrete fence posts; concrete gate posts; corner posts; clothes line posts; grape arbor posts; tanks; troughs; cisterns; hog wallows; feeding floors and barnyard pavements; foundations; well curbs and platforms; indoor floors; sidewalks; steps; concrete hotbeds and cold frames; concrete slab roofs; walls for buildings; repairing leaks in tanks and cisterns; and all topics associated with these subjects as bearing upon securing the best results from concrete are dwelt upon at sufficient length in plain every-day English so that the inexperienced person desiring to undertake a piece of concrete construction can, by following the directions set forth in this book, secure 100 per cent success every time. A number of convenient and practical tables for estimating quantities, and some practical examples, are also given. 150 pages, 51 illustrations. **Price, \$1.00**

### **Concrete From Sand Molds.**

By A. A. HOUGHTON. A practical work treating on a process which has heretofore been held as a trade secret by the few who possessed it, and which will successfully mold every and any class of ornamental concrete work. The process of molding concrete with sand molds is of the utmost practical value, possessing the manifold advantages of a low cost of molds, the ease and rapidity of operation, perfect details to all ornamental designs, density and increased strength of the concrete, perfect curing of the work without attention and the easy removal of the molds regardless of any undercutting the design may have. 192 pages. Fully illustrated. Cloth. **Price, \$2.00**

### **Ornamental Concrete Without Molds.**

By A. A. HOUGHTON. The process for making ornamental concrete without molds has long been held as a secret, and now, for the first time, this process is given to the public. The book reveals the secret and is the only book published

which explains a simple, practical method whereby the concrete worker is enabled, by employing wood and metal templates of different designs, to mold or model in concrete any cornice, archivolt, column, pedestal, base cap, urn or pier in a monolithic form—right upon the job. These may be molded in units or blocks, and then built up to suit the specifications demanded. This work is fully illustrated, with detailed engravings. Cloth. **Price, \$2.00**

### **Popular Handbook for Cement and Concrete Users.**

By MYRON H. LEWIS. Everything of value to the concrete user is contained, including kinds of cement employed in construction, concrete architecture, inspection and testing, waterproofing, coloring and painting, rules tables, working and cost data. The book comprises thirty-three chapters. A valuable addition to the library of every cement and concrete user. Cloth, 430 pages, 126 illustrations. **Price, \$3.00**

### **Waterproofing Concrete.**

By MYRON H. LEWIS. Modern methods of waterproofing concrete and other structures. A condensed statement of the principles, rules and precautions to be observed in waterproofing and damp-proofing structures and structural materials. Paper binding. Illustrated. Second Edition. **75 cents**

## **DIES—METAL WORK**

### **Dies; Their Construction and Use for the Modern Working of Sheet Metals.**

By J. V. WOODWORTH. A new book by a practical man, for those who wish to know the latest practice in the working of sheet metals. It shows how dies are designed, made and used, and those who are engaged in this line of work can secure many valuable suggestions. Sixth revised edition. 525 illustrations, 394 pages. Cloth. **Price, \$3.50**

### **Punches, Dies and Tools for Manufacturing in Presses.**

By J. V. WOODWORTH. An encyclopedia of die-making, punch-making, die-sinking, sheet-metal working, and making of special tools, subpresses, devices and mechanical combinations for punching, cutting, bending, forming, piercing, drawing, compressing, and assembling sheet-metal parts and also articles of other materials in machine tools. This is a distinct work from the author's book entitled "Dies; Their Construction and Use." 500 pages, 700 engravings. Second edition. Cloth. **Price, \$4.50**

### **Drop Forging, Die-Sinking and Machine-Forming of Steel.**

By J. V. WOODWORTH. The processes of die-sinking and force-making, which are thoroughly described and illustrated in this admirable work, are rarely to be found explained in such a clear and concise manner as is here set forth. The process of die-sinking relates to the engraving or sinking

of the female or lower dies, such as are used for drop forgings, hot and cold machine forging, swedging and the press working of metals. The process of force-making relates to the engraving or raising of the male or upper dies used in producing the lower dies for the press-forming and machine-forging of duplicate parts of metal. The book contains eleven chapters, and the information contained in these chapters is just what will prove most valuable to the forged-metal worker. 304 detailed illustrations. 341 pages, cloth. **Price, \$3.00**

## **DICTIONARIES**

### **Aviation Terms—English-French; French-English.**

A complete glossary of practically all terms used in aviation, having lists in both French and English with equivalents in either language. A very valuable book compiled by Lieuts. Victor W. Pagé and Paul Montariol. **Price, \$1.00**

### **Standard Electrical Dictionary.**

By PROF. T. O'CONNOR SLOANE. Just issued an entirely new edition brought up to date and greatly enlarged—as a reference book this work is beyond comparison as it contains over 700 pages, nearly 500 illustrations, and definitions of about 6,000 distinct words, terms and phrases. The definitions are terse and concise and includes every term used in electrical science.

In its arrangement and typography the book is very convenient. The word or term defined is printed in black faced type which readily catches the eye, while the body of the page is in smaller but distinct type. The definitions are well worded, and so as to be understood by the non-technical reader. The general plan is to give an exact, concise definition, and then amplify and explain in a more popular way. Synonyms are also given, and references to other words and phrases are made. This work is absolutely indispensable to all in any way interested in electrical science, from the higher electrical expert to the everyday electrical workman. In fact, it should be in the possession of all who desire to keep abreast with the progress of this branch of science. 1920 enlarged edition. Nearly 800 pages and nearly 400 illustrations. **Price, \$5.00**

## **DRAWING—SKETCHING PAPER**

### **Linear Perspective Self-Taught.**

By HERMAN T. C. KRAUS. This work gives the theory and practice of linear perspective, as used in architectural, engineering and mechanical drawings. The arrangement of the book is good; the plate is on the left-hand, while the descriptive text follows on the opposite page, so as to be readily referred to. A self-explanatory linear perspective chart is included in the second revised edition. Cloth. **Price, \$3.00**

## Self-Taught Mechanical Drawing and Elementary Machine Design.

By F. L. SYLVESTER, M.E., Draftsman, with additions by Erik Oberg, associate editor of "Machinery." A practical elementary treatise on Mechanical Drawing and Machine Design, comprising the first principles of geometric and mechanical drawing, workshop mathematics, mechanics, strength of materials and the calculation and design of machine details, compiled for the use of practical mechanics and young draftsmen. 330 pages, 215 engravings, cloth. **Price, \$2.50**

## A New Sketching Paper.

A new specially ruled paper to enable you to make sketches or drawings in isometric perspective without any figuring or fussing. It is being used for shop details as well as for assembly drawings, as it makes one sketch do the work of three, and no workman can help seeing just what is wanted. Pads of 40 sheets, 6 x 9 inches, **Price, 25c.**; 9 x 12 inches, **Price, 50c.**; 12 x 18 inches, **Price, \$1.00.**

## Practical Perspective.

By RICHARDS and COLVIN. Shows just how to make all kinds of mechanical drawings in the only practical perspective isometric. Makes everything plain so that any mechanic can understand a sketch or drawing in this way. Saves time in the drawing room and mistakes in the shops. Contains practical examples of various classes of work. Third edition. Limp cloth. **Price, 75 cents**

# ELECTRICITY

## Arithmetic of Electricity.

By PROF. T. O'CONOR SLOANE. A practical treatise on electrical calculations of all kinds reduced to a series of rules, all of the simplest forms, and involving only ordinary arithmetic; each rule illustrated by one or more practical problems with detailed solution of each one. This book is classed among the most useful works published on the science of electricity, covering as it does the mathematics of electricity in a manner that will attract the attention of those who are not familiar with algebraical formulas. 200 pages. 1920 Revised and Enlarged edition. **Price, \$1.50**

## Dynamo Building for Amateurs, or How to Construct a Fifty Watt Dynamo.

By ARTHUR J. WEED. A practical treatise showing in detail the construction of a small dynamo or motor, the entire machine work of which can be done on a small foot lathe. Dimensioned working drawings are given for each piece of machine work, and each operation is clearly described. This machine, when used as a dynamo, has an output of fifty watts; when used as a motor it will drive a small drill press or lathe. It can be used to drive a sewing machine on any and all ordinary work. The book is illustrated with more than sixty original engravings showing the actual construction of the different parts. **Price, Cloth, \$1.00**

## Electric Bells.

By M. B. SLEEPER. A complete treatise for the practical worker in installing, operating and testing bell circuits, burglar alarms, thermostats and other apparatus used with electric bells. Both the electrician and the experimenter will find in this book new material which is essential in their work. Tools, bells, batteries, unusual circuits, burglar alarms, annunciators, systems, thermostats, circuit breakers, time alarms, and other apparatus used in bell circuits are described from the standpoints of their application, construction, and repair. The detailed instructions for building the apparatus will appeal to the experimenter particularly. The practical worker will find the chapters on Wiring Calculation of Wire Sizes and Magnet Windings, Upkeep of Systems and the Location of Faults of the greatest value in their work. 124 pages. Fully illustrated. **Price, 75 cents.**

## Commutator Construction

By WM. BAXTER, JR. The business end of dynamo or motor of the direct current type is the commutator. This book goes into the designing, building and maintenance of commutators, shows how to locate troubles and how to remedy them; everyone who fusses with dynamos needs this. Fourth edition. **Price, 35 cents.**

## Dynamos and Electric Motors and All About Them.

By EDWARD TREVERT. This volume gives practical directions for building a two H. P. Dynamo of the Edison type capable of lighting about fifty Mazda lamps of the 20 watt size. In addition, it gives directions for building two small electric motors suitable for running sewing machines. The concluding chapter describes the construction of a simple bichromate battery adapted for running electric motors. 96 pages. Fully illustrated with detail drawings. Cloth. **Price, \$1.00.**

## Construction of a Transatlantic Wireless Receiving Set.

By L. G. PACENT and T. S. CURTIS. A work for the Radio student who desires to construct and operate apparatus that will permit of the reception of messages from the large stations in Europe with an aerial of amateur proportions. 36 pages. 23 illustrations, cloth. **Price, 35 cents.**

## Electric Toy Making, Dynamo Building and Electric Motor Construction.

This work treats of the making at home of electrical toys, electrical apparatus, motors, dynamos and instruments in general and is designed to bring within the reach of young and old the manufacture of genuine and useful electrical appliances. 210 pages, cloth. Fully illustrated. Twentieth edition, enlarged. **Price, \$1.50**

## Experimental High Frequency Apparatus, How to Make and Use It.

By THOMAS STANLEY CURTIS. 69 pages, illustrated. **Price, 50 cents.**

### **Electrician's Handy Book.**

By PROF. T. O'CONOR SLOANE. This work has just been revised and much enlarged. It is intended for the practical electrician who has to make things go. The entire field of electricity is covered within its pages. It is a work of the most modern practice, written in a clear, comprehensive manner, and covers the subject thoroughly, beginning at the A B C of the subject, and gradually takes you to the more advanced branches of the science. It teaches you just what you should know about electricity. A practical work for the practical man. Contains forty-eight chapters.

The publishers consider themselves fortunate in having secured the services of such a well and favorably known writer as Prof. Sloane, who has with the greatest care completed a master work in concise form on this all important subject. 600 engravings, 840 pages, handsomely bound in cloth. 1920 Edition.

**Price, \$4.00**

### **Electricity Simplified.**

By PROF. T. O'CONOR SLOANE. The object of 'Electricity Simplified' is to make the subject as plain as possible and to show what the modern conception of electricity is; to show how two plates of different metals immersed in acid can send a message around the globe; to explain how a bundle of copper wire rotated by a steam engine can be the agent in lighting our streets, to tell what the volt, ohm and ampere are, and what high and low tension mean; and to answer the questions that perpetually arise in the mind in this age of electricity. 172 pages. Illustrated. Thirteenth edition. Cloth.

**Price, \$1.50**

### **Electric Wiring, Diagrams and Switchboards.**

By NEWTON HARRISON, with additions by THOMAS POPPE. This is the only complete work issued showing and telling you what you should know about direct and alternating current wiring. The work is free from advanced technicalities and mathematics, arithmetic being used throughout. It is in every respect a handy, well-written, instructive, comprehensive volume on wiring for the wireman, foreman, contractor or electrician. Third revised edition. 303 pages, 130 illustrations. Cloth.

**Price, \$2.50**

### **House Wiring.**

By THOMAS W. POPPE. Describing and illustrating up-to-date methods of installing electric light wiring. Contains just the information needed for successful wiring of a building. Fully illustrated with diagrams and plans. It solves all wiring problems and contains nothing that conflicts with the rulings of the National Board of Fire Underwriters. Third edition revised and enlarged. 125 pages, fully illustrated, flexible cloth.

**Price, 75 cents**

### **High Frequency Apparatus, Its Construction and Practical Application.**

By THOMAS STANLEY CURTIS. The most comprehensive and thorough work on this interesting subject ever produced. The book is essentially practical in its treatment and it constitutes an accurate record of the researches of its author over a period of several years, during which time dozens of coils were built and experimented with. New revised and enlarged 1920 edition. 275 pages.

**Price, \$3.00**

### **How to Become a Successful Electrician.**

By PROF. T. O'CONOR SLOANE. An interesting book from cover to cover. Telling in simplest language the surest and easiest way to become a successful electrician. The studies to be followed, methods of work, field of operation and the requirements of the successful electrician are pointed out and fully explained. 202 pages. Illustrated. Eighteenth revised edition. Cloth.

**Price, \$1.50**

### **Standard Electrical Dictionary.**

By PROF. T. O'CONOR SLOANE. Just issued an entirely new edition brought up to date and greatly enlarged—as a reference-book this work is beyond comparison as it contains over 700 pages, nearly 500 illustrations, and definitions of about 6,000 distinct words, terms and phrases. The definitions are terse and concise and includes every term used in electrical science.

In its arrangement and typography the book is very convenient. The word or term defined is printed in black faced type which readily catches the eye, while the body of the page is in smaller but distinct type. The definitions are well worded, and so as to be understood by the non-technical reader. The general plan is to give an exact, concise definition, and then amplify and explain in a more popular way. Synonyms are also given, and references to other words and phrases are made. This work is absolutely indispensable to all in any way interested in electrical science, from the higher electrical expert to the everyday electrical workman. In fact, it should be in the possession of all who desire to keep abreast with the progress of this branch of science. 1920 enlarged edition. Nearly 800 pages. 400 illustrations.

**Price, \$5.00**

### **Storage Batteries Simplified.**

By VICTOR W. PAGÉ, M.S.A.E. This is the most thorough and authoritative treatise ever published on this subject. It is written in easily understandable, non-technical language so that any one may grasp the basic principles of storage battery action as well as their practical industrial applications. All electric and gasoline automobiles use storage batteries. Every automobile repairman, dealer or salesman should have a good knowledge of maintenance and repair of these important elements of the motor car mechanism. This book not only tells how to charge, care for and rebuild storage batteries but also outlines all the industrial uses. Learn how they run street cars, locomotives and factory trucks. Get an understanding of the important functions they perform in submarine boats, isolated lighting plants, railway switch and signal systems, marine applications, etc. This book tells how they are used in central station standby service, for starting automobile motors and in ignition systems. Every practical use of the modern storage battery is outlined in this treatise. 208 pages, fully illustrated.

**Price, \$2.00**

### **Wiring a House.**

By HERBERT PRATT. Shows a house already built; tells just how to start about wiring it; where to begin; what wire to use; how to run it according to insurance rules; in fact, just the information you need. Directions apply equally to a shop. Fourth edition.

**Price, 35 cents**

## Switchboards.

By WILLIAM BAXTER, JR. This book appeals to every engineer and electrician who wants to know the practical side of things. All sorts and conditions of dynamos, connections and circuits are shown by diagram and illustrate just how the switchboard should be connected. Includes direct and alternating current boards, also those for arc lighting, incandescent and power circuits. Special treatment on high voltage boards for power transmission. Second edition. 190 pages. Illustrated. **Price, \$2.00**

## Telephone Construction, Installation, Wiring, Operation and Maintenance.

By W. H. RADCLIFFE and H. C. CUSHING. This book gives the principles of construction and operation of both the Bell and Independent instruments; approved methods of installing and wiring them; the means of protecting them from lightning and abnormal currents; their connection together for operation as series or bridging stations; and rules for their inspection and maintenance. Line wiring and the wiring and operation of special telephone systems are also treated. 224 pages, 132 illustrations. Second revised edition. **Price, \$1.50**

## Wireless Telegraphy and Telephony Simply Explained.

By ALFRED P. MORGAN. This is undoubtedly one of the most complete and comprehensive treatises on the subject ever published, and a close study of its pages will enable one to master all the details of the wireless transmission of messages. The author has filled a long-felt want and has succeeded in furnishing a lucid, comprehensible explanation in simple language of the theory and practise of wireless telegraphy and telephony. Third edition. 154 pages, 156 engravings. **Price, \$1.50**

## Radio Time Signal Receiver.

By AUSTIN C. LESCABOURA. This new book, "A Radio Time Signal Receiver," tells you how to build a simple outfit designed expressly for the beginner. You can build the outfit in your own workshop and install them for jewelers either on a one-payment or a rental basis. The apparatus is of such simple design that it may be made by the average amateur mechanic possessing a few ordinary tools. 42 pages. Paper. **Price, 35 cents**

## Experimental Wireless Stations.

By P. E. EDELMAN. The theory, design, construction and operation is fully treated including Wireless Telegraphy, Vacuum Tube, and quenched spark systems. The new enlarged 1920 edition is just issued and is strictly up to date, correct and complete. This book tells how to make apparatus to not only hear all telephoned radio messages, but also how to make simple equipment that works for transmission over reasonably long distances. Then there is a host of new information included. The first and only book to give you all the recent important radio improvements, some of which have never before been published. 24 chapters. 167 illustrations. **Price, \$2.50**

## FUEL

### Combustion of Coal and the Prevention of Smoke.

By WM. M. BARR. This book has been prepared with special reference to the generation of heat by the combustion of the common fuels found in the United States, and deals particularly with the conditions necessary to the economic and smokeless combustion of bituminous coals in stationary and locomotive steam boilers. The presentation of this important subject is systematic and progressive. The arrangement of the book is in a series of practical questions, to which are appended accurate answers, which describe in language, free from technicalities, the several processes involved in the furnace combustion of American fuels; it clearly states the essential requisites for perfect combustion, and points out the best methods for furnace construction for obtaining the greatest quantity of heat from any given quality of coal. Nearly 350 pages, fully illustrated. Fifth edition. **Price, \$1.50**

### Smoke Prevention and Fuel Economy.

By BOOTH and KERSHAW. As the title indicates, this book of 197 pages and 75 illustrations deals with the problem of complete combustion, which it treats from the chemical and mechanical standpoints, besides pointing out the economical and humanitarian aspects of the question. **Price, \$3.00**

## GAS ENGINES AND GAS

### Gas, Gasoline and Oil Engines.

By GARDNER D. HISCOX. Revised by VICTOR W. PAGÉ. Just issued new, revised and enlarged edition. Every user of a gas engine needs this book. Simple, instructive and right up-to-date. The only complete work on the subject. Tells all about internal combustion engineering, treating exhaustively on the design, construction and practical application of all forms of gas, gasoline, kerosene and crude petroleum-oil engines. Describes minutely all auxiliary systems, such as lubrication, carburetion and ignition. Considers the theory and management of all forms of explosive motors for stationary and marine work, automobiles, aeroplanes and motorcycles. Includes also Producer Gas and Its Production. Invaluable instructions for all students, gas-engine owners, gas-engineers, patent experts, designers, mechanics, draftsmen and all having to do with the modern power. Illustrated by over 400 engravings, many specially made from engineering drawings, all in correct proportion. Nearly 700 octavo pages and 500 engravings. **Price, net, \$3.00**

### Gasoline Engines: Their Operation, Use and Care.

By A. HYATT VERRILL. A comprehensive, simple and practical work, treating of gasoline engines for stationary, marine or vehicle use; their construction, design, management, care, operation, repair, installation and troubles. A complete glossary of technical terms and an alphabetically arranged table of troubles and symptoms form a most valuable and unique feature of the book.  $5\frac{1}{4} \times 7\frac{1}{2}$ . Cloth. 275 pages, 152 illustrations. **Price, \$2.00**

### **Gas Engine Construction.**

Or How to Build a Half-Horse-power Gas Engine. By PARSELL and WEED. A practical treatise describing the theory and principles of the action of gas engines of various types, and the design and construction of a half-horse-power gas engine, with illustrations of the work in actual progress, together with dimensioned working drawings giving clearly the sizes of the various details. 300 pages. Third edition. Cloth. **Price, \$3.00**

### **Chemistry of Gas Manufacture.**

By H. M. ROYLES. This book covers points likely to arise in the ordinary course of the duties of the engineer or manager of a gas works not large enough to necessitate the employment of a separate chemical staff. It treats of the testing of the raw materials employed in the manufacture of illuminating coal gas and of the gas produced. The preparation of standard solutions is given as well as the chemical and physical examination of gas coal.  $5\frac{1}{4} \times 8\frac{3}{4}$ . Cloth. 328 pages, 82 illustrations, 1 colored plate. **Price, \$5.00**

### **Modern Gas Engines and Producer Gas Plants.**

By R. E. MATROT, M.E. A practical treatise of 320 pages, fully illustrated by 175 detailed illustrations, setting forth the principles of gas engines and producer design, the selection and installation of an engine, conditions of perfect operation, producer-gas engines and their possibilities, the care of gas engines and producer-gas plants, with a chapter on volatile hydrocarbon and oil engines. This book has been endorsed by Dugal Clerk as a most useful work for all interested in gas engine installation and producer gas. **\$3.00**

### **The Gasoline Engine on the Farm: Its Operation, Repair and Uses.**

By XENO W. PUTNAM. A useful and practical treatise on the modern gasoline and kerosene engine, its construction, management, repair and the many uses to which it can be applied in present-day farm life. It considers all the various household, shop and field uses of this up-to-date motor and includes chapters on engine installation, power transmission and the best arrangement of the power plant in reference to the work.  $5\frac{1}{4} \times 7\frac{1}{2}$ . Cloth. 527 pages, 179 illustrations. **Price, \$3.00**

### **How to Run and Install Two- and Four-Cycle Marine, Gasoline Engines.**

By C. VON CULIN. New revised and enlarged edition just issued. The object of this little book is to furnish a pocket instructor for the beginner, the busy man who uses an engine for pleasure or profit, but who does not have the time or inclination for a technical book, but simply to thoroughly understand how to properly operate, install and care for his own engine. The index refers to each trouble, remedy and subject alphabetically. Being a quick reference to find the cause, remedy and prevention for troubles, and to become an expert with his own engine. Pocket size. Paper binding. **Price, 25 cents**

### **Modern Gas Tractor, Its Construction, Utility, Operation and Repair.**

By VICTOR W. PAGE. Treats exhaustively on the design and construction of farm tractors and tractor power-plants, and gives complete instructions on their care, operation and repair. All types and sizes of gasoline, kerosene and oil tractors are described, and every phase of traction engineering practice fully covered. Invaluable to all desiring reliable information on gas motor propelled traction engines and their use. Second edition revised by much additional matter.  $5\frac{1}{4} \times 7\frac{1}{2}$ . Cloth, 504 pages, 228 illustrations. 3 folding plates. **Price, \$3.00**

## **GEARING AND CAMS**

### **Bevel Gear Tables.**

By D. AG. ENGSTROM. No one who has to do with bevel gears in any way should be without this book. The designer and draftsman will find it a great convenience, while to the machinist who turns up the blanks or cuts the teeth it is invaluable, as all needed dimensions are given and no facy figuring need be done. Third edition. Cloth. **\$1.50**

### **Change Gear Devices.**

By OSCAR E. FERRIGO. A book for every designer, draftsman and mechanic who is interested in feed changes for any kind of machines. This shows what has been done and how. Gives plans, patents and all information that you need. Saves hunting through patent records and reinventing old ideas. A standard work of reference. Third edition. **\$1.50**

### **Drafting of Cams.**

By LOUIS ROUILLION. The laying out of cams is a serious problem unless you know how to go at it right. This puts you on the right road for practically any kind of cam you are likely to run up against. Third edition. **35 cents**

## **HYDRAULICS**

### **Hydraulic Engineering.**

By GARDNER D. HISCOX. A treatise on the properties, power, and resources of water for all purposes. Including the measurements of streams; the flow of water in pipes or conduits; the horse-power of falling water; turbine and impact water-wheels; wave-motors, centrifugal, reciprocating and air-lift pumps. With 300 figures and diagrams and 36 practical tables. 320 pages. **Price, \$4.50**

## **ICE AND REFRIGERATION**

### **Pocketbook of Refrigeration and Ice Making.**

By A. J. WALLIS-TAYLOR. This is one of the latest and most comprehensive reference books published on the subject of refrigeration and cold storage. It explains the properties

and refrigerating effect of the different fluids in use, the management of refrigerating machinery and the construction and insulation of cold rooms with their required pipe surface for different degrees of cold; freezing mixtures and non-freezing brines, temperatures of cold rooms for all kinds of provisions, cold storage charges for all classes of goods, ice making and storage of ice, data and memoranda for constant reference by refrigerating engineers, with nearly one hundred tables containing valuable references to every fact and condition required in the installment and operation of a refrigerating plant. New edition just published. **Price, \$2.00**

## INVENTIONS—PATENTS

### **Inventor's Manual, How to Make a Patent Pay.**

This is a book designed as a guide to inventors in perfecting their inventions, taking out their patents, and disposing of them. It is not in any sense a Patent Solicitor's circular nor a Patent Broker's advertisement. No advertisements of any description appear in the work. It is a book containing a quarter of a century's experience of a successful inventor, together with notes based upon the experience of many other inventors. Revised and enlarged second edition. Nearly 150 pages. Illustrated. **Price \$1.25**

## KNOTS

### **Knots, Splices and Rope Work.**

By A. HYATT VERRILL. This is a practical book giving complete and simple directions for making all the most useful and ornamental knots in common use, with chapters on Splicing, Pointing, Seizing, Serving, etc. This book is fully illustrated with 134 original engravings, which show how each knot, tie or splice is formed, and its appearance when finished. The book will be found of the greatest value to campers, yachtsmen, travelers or Boy Scouts, in fact, to anyone having occasion to use or handle rope or knots for any purpose. The book is thoroughly reliable and practical, and is not only a guide but a teacher. It is the standard work on the subject. Second edition revised. 128 pages, 154 original engravings. **Price, \$1.00**

## LATHE WORK

### **Complete Practical Machinist.**

By JOSHUA ROSE. The new, twentieth revised and enlarged edition is now ready. This is one of the best-known books on machine-shop work, and written for the practical workman in the language of the workshop. It gives full, practical instructions on the use of all kinds of metal-working tools, both hand and machine, and tells how the work should be properly done. It covers lathe work, vise work, drills and drilling, taps and dies, hardening and tempering, the making and use of tools, tool grinding, marking out work, machine tools, etc. No machinist's library is complete without this volume. 547 pages, 432 illustrations. (1920.) **Price \$3.00**

## **The Lathe—Its Design, Construction and Operation, With Practical Examples of Lathe Work.**

By OSCAR E. PERRIGO. A new revised edition, and the only complete American work on the subject, written by a man who knows not only how work ought to be done, but who also knows how to do it, and how to convey this knowledge to others. It is strictly up-to-date in its descriptions and illustrations. Lathe history and the relations of the lathe to manufacturing are given; also a description of the various devices for feeds and thread cutting mechanisms from early efforts in this direction to the present time. Lathe design is thoroughly discussed, including back gearing, driving cones, thread-cutting gears, and all the essential element of the modern lathe. The classification of lathes is taken up, giving the essential differences of the several types of lathes including, as is usually understood, engine lathes, bench lathes, speed lathes, forge lathes, gap lathes, pulley lathes, forming lathes, multiple-spindle lathes, rapid-reduction lathes, precision lathes, turret lathes, special lathes, electrically-driven lathes, etc. In addition to the complete exposition on construction and design, much practical matter on lathe installation, care and operation has been incorporated in the enlarged new edition. All kinds of lathe attachments for drilling, milling, etc., are described and complete instructions are given to enable the novice machinist to grasp the art of lathe operation as well as the principles involved in design. A number of difficult machining operations are described at length and illustrated. The new edition has nearly 500 pages and 350 illustrations. **Price, \$3.00**

### **Turning and Boring Tapers.**

By FRED H. COLVIN. There are two ways to turn tapers; the right way and one other. This treatise has to do with the right way; it tells you how to start the work properly, how to set the lathe, what tools to use and how to use them, and forty and one other little things that you should follow. Fourth edition. **Price, 35 cents**

## LIQUID AIR

### **Liquid Air and the Liquefaction of Gases.**

By T. O'CONOR SLOANE. The third revised edition of this book has just been issued. Much new material is added to it; and the all important uses of liquid air and gas processes in modern industry, in the production especially of nitrogen compounds, are described. The book gives the history of the theory, discovery, and manufacture of Liquid Air, and contains an illustrated description of all the experiments that have excited the wonder of audiences all over the country. It shows how liquid air, like water, is carried hundreds of miles and is handled in open buckets. It tells what may be expected from it in the near future. A book that renders simple one of the most perplexing chemical problems of the century. Startling developments illustrated by actual experiments. It is not only a work of scientific interest and authority, but is intended for the general reader, being written in a popular style—easily understood by everyone. 400 pages fully illustrated. (1920.) **Price, \$3.00**

## LOCOMOTIVE ENGINEERING

### **Air-Brake Catechism.**

By ROBERT H. BLACKALL. This book is a standard text book. It is the only practical and complete work published. Treats on the equipment manufactured by the Westinghouse Air Brake Company, including the E-T Locomotive Brake Equipment, the K (Quick-Service) Triple Valve for freight service; the L High Speed Triple Valve; the P-C Passenger Brake Equipment, and the Cross Compound Pump. The operation of all parts of the apparatus is explained in detail and a practical way of locating their peculiarities and remedying their defects is given. Endorsed and used by air-brake instructors and examiners on nearly every railroad in the United States. Twenty-sixth edition. 411 pages, fully illustrated with folding plates and diagrams. New edition.

**Price, \$2.50**

### **Application of Highly Superheated Steam to Locomotives.**

By ROBERT GARBE. A practical book which cannot be recommended too highly to those motive-power men who are anxious to maintain the highest efficiency in their locomotives. Contains special chapters on Generation of Highly Superheated Steam; Superheated Steam and the Two-Cylinder Simple Engine; Compounding and Superheating; Designs of Locomotive Superheaters; Constructive Details of Locomotives Using Highly Superheated Steam. Experimental and Working Results. Illustrated with folding plates and tables. Cloth.

**Price, \$3.00**

### **Combustion of Coal and the Prevention of Smoke.**

By WM. M. BARR. To be a success a fireman must be "Light on Coal." He must keep his fire in good condition, and prevent, as far as possible, the smoke nuisance. To do this, he should know how coal burns, how smoke is formed and the proper burning of fuel to obtain the best results. He can learn this, and more too, from Barr's "Combustion of Coal." It is an absolute authority on all questions relating to the firing of a locomotive. Fifth edition. Nearly 350 pages, fully illustrated.

**Price, \$1.50**

### **Diary of a Round-House Foreman.**

By T. S. REILLY. This is the greatest book of railroad experiences ever published. Containing a fund of information and suggestions along the line of handling men, organizing, etc., that one cannot afford to miss. 176 pages.

**Price, \$1.25**

### **Link Motions, Valves and Valve Setting.**

By FRED H. COLVIN, Associate Editor of "American Machinist." A handy book that clears up the mysteries of valve setting. Shows the different valve gears in use, how they work, and why. Piston and slide valves of different types are illustrated and explained. A book that every railroad man in the motive-power department ought to have. Fully illustrated. New revised and enlarged edition just published.

**Price, 75 cents**

### **Train Rule Examinations Made Easy.**

By G. E. COLLINGWOOD. This is the only practical work on train rules in print. Every detail is covered, and puzzling points are explained in simple, comprehensive language, making it a practical treatise for the train dispatcher, engineer, trainman and all others who have to do with the movements of trains. Contains complete and reliable information of the Standard Code of Train Rules for single track. Shows signals in colors, as used on the different roads. Explains fully the practical application of train orders, giving a clear and definite understanding of all orders which may be used. Second edition revised. 256 pages. Fully illustrated with train signals in colors.

**Price, \$1.50**

### **Locomotive Boiler Construction.**

By FRANK A. KLEINHANS. The only book showing how locomotive boilers are built in modern shops. Shows all types of boilers used; gives details of construction; practical facts, such as life of riveting punches and dies, work done per day, allowance for bending and flanging sheets and other data that means dollars to any railroad man. Second edition. 451 pages, 334 illustrations. Six folding plates. Cloth.

**Price, \$3.50**

### **Locomotive Breakdowns and Their Remedies.**

By GEO. L. FOWLER. Revised by Wm. W. Wood, Air-Brake Instructor. Pocket edition. It is out of the question to try and tell you about every subject that is covered in this pocket edition of Locomotive Breakdowns. Just imagine all the common troubles that an engineer may expect to happen some time, and then add all of the unexpected ones, troubles that could occur, but that you had never thought about, and you will find that they are all treated with the very best methods of repair. Walschaert Locomotive Valve Gear Troubles, Electric Headlight Troubles, as well as Questions and Answers on the Air Brake, are all included. Eighth edition. 294 pages. Fully illustrated.

**Price, \$1.50**

### **Locomotive Catechism.**

By ROBERT GRIMSHAW. Twenty-eighth revised and enlarged edition. This may well be called an encyclopedia of the locomotive. Contains over 4,000 examination questions with their answers, including among them those asked at the first, second and third year's examinations. 825 pages, 437 illustrations and 3 folding plates.

**Price, \$2.50**

### **Westinghouse E. T. Air-Brake Instruction Pocket-book Catechism.**

By WM. W. WOOD, Air-Brake Instructor. A practical work containing examination questions and answers on the E. T. Equipment. Covering what the E. T. Brake is. How it should be operated. What to do when defective. Not a question can be asked of the engineman up for promotion on either the No. 5 or the No. 6 E. T. equipment that is not asked and answered in the book. If you want to thoroughly understand the E. T. equipment get a copy of this book. It covers every detail. Makes air-brake troubles and examinations easy. Fully illustrated with colored plates, showing various pressures. Cloth. (1920.)

**Price, \$2.50**



## **Practical Instructor and Reference Book for Locomotive Firemen and Engineers.**

By CHAS. F. LOCKHART. An entirely new book on the locomotive. It appeals to every railroad man, as it tells him how things are done and the right way to do them. Written by a man who has had years of practical experience in locomotive shops and on the road firing and running. The information given in this book cannot be found in any other similar treatise. Eight hundred and fifty-one questions with their answers are included, which will prove specially helpful to those preparing for examination. 368 pages, 88 illustrations. Cloth. **Price, \$2.00**

## **Prevention of Railroad Accidents, or Safety in Railroad.**

By GEORGE BRADSHAW. This book is a heart-to-heart talk with railroad employees, dealing with facts, not theories, and showing the men in the ranks, from every-day experience, how accidents occur and how they may be avoided. The book is illustrated with seventy original photographs and drawings showing the safe and unsafe methods of work. No visionary schemes, no ideal pictures. Just plain facts and practical suggestions are given. Every railroad employee who reads the book is a better and safer man to have in railroad service. It gives just the information which will be the means of preventing many injuries and deaths. All railroad employees should procure a copy; read it, and do their part in preventing accidents. 169 pages. Pocket size. Fully illustrated. **Price, 50 cents**

## **Walschaert Locomotive Valve Gear.**

By WM. W. WOOD. If you would thoroughly understand the Walschaert Valve Gear, you should possess a copy of this book. The author divides the subject into four divisions, as follows: I. Analysis of the gear. II. Designing and erection of the gear. III. Advantages of the gear. IV. Questions and answers relating to the Walschaert Valve Gear. This book is specially valuable to those preparing for promotion. Third edition. 245 pages. Fully illustrated. Cloth. **Price, \$2.50**

## **MACHINE SHOP PRACTICE**

### **Modern Machine Shop Construction, Equipment and Management.**

By OSCAR E. PERRIGO. The only work published that describes the Modern Machine Shop or Manufacturing Plant from the time the grass is growing on the site intended for it until the finished product is shipped. Just the book needed by those contemplating the erection of modern shop buildings, the rebuilding and reorganization of old ones or the introduction of Modern Shop Methods, Time and Cost Systems. It is a book written and illustrated by a practical shop man for practical shop men who are too busy to read theories and want facts. It is the most complete all-around book of its kind ever published. Second edition. 384 pages, 219 original and specially-made illustrations. **Price, \$6.00**

## **EVERY PRACTICAL MAN NEEDS**

**A MAGAZINE WHICH WILL TELL HIM  
HOW TO MAKE AND DO THINGS**

HAVE US ENTER YOUR SUBSCRIPTION to the best mechanical magazine on the market. Only Two Dollars a year for twelve numbers. Subscribe to-day to

## **EVERYDAY ENGINEERING**

A monthly magazine devoted to practical mechanics for everyday men. Its aim is to popularize engineering as a science, teaching the elements of applied mechanics and electricity in a straightforward and understandable manner. The magazine maintains its own experimental laboratory, where the devices described in articles submitted to the Editor are first tried out and tested before they are published. This important innovation places the standard of the published material very high, and it insures accuracy and dependability.

The magazine is the only one in this country that specializes in practical model building. Articles in past issues have given comprehensive designs for many model boats, including submarines and chasers, model steam and gasoline engines, electric motors and generators, etc., etc. This feature is a permanent one in the magazine.

Another popular department is that devoted to automobiles and airplanes. Care, maintenance, and operation receive full and authoritative treatment. Every article is written from the practical, everyday man standpoint, rather than from that of the professional.

The magazine entertains while it instructs. It is a journal of practical, dependable information, given in a style that it may be readily assimilated and applied by the man with little or no technical training. The aim is to place before the man who leans toward practical mechanics a series of concise, crisp, readable talks on what is going on and *how it is done*. These articles are profusely illustrated with clear, snappy photographs, specially posed to illustrate the subject in the magazine's own studio by its own staff of technically-trained illustrators and editors.

The subscription price of the magazine is two dollars per year in U. S., two dollars and twenty-five cents in Canada and three dollars in foreign countries. Sample copy sent on receipt of twenty cents.

### Machine Shop Arithmetic.

By COLVIN-CHENEY. Most popular book for shop men. Shows how all shop problems are worked out and "why." Includes change gears for cutting any threads; drills, taps, shank and force fits; metric system of measurements and threads. Used by all classes of mechanics and for instruction in V. M. C. A. and other schools. Seventh edition. 131 pages. Price, 75 cents.

### Abrasives and Abrasive Wheels.

By FRED B. JACOBS. A new book for everyone interested in abrasives or grinding. A careful reading of the book will not only make mechanics better able to use abrasives intelligently, but it will also tell the shop superintendent of many short cuts and efficiency-increasing kinks. The economic advantage in using large grinding wheels are fully explained, together with many other things that will tend to give the superintendent or workman a keen insight into abrasive engineering. 340 pages, 200 illustrations. This is an indispensable book for every machinist. Price, \$3.00

### American Tool Making and Interchangeable Manufacturing.

By J. V. WOODWORTH. In its 500-odd pages the one subject only, Tool Making, and whatever relates thereto, is dealt with. The work stands without a rival. It is a complete practical treatise on the art of American Tool Making and system of interchangeable manufacturing as carried on to-day in the United States. In it are described and illustrated all of the different types and classes of small tools, fixtures, devices and special appliances which are in general use in all machine-manufacturing and metal-working establishments where economy, capacity and interchangeability in the production of machined metal parts are imperative. The science of jig making is exhaustively discussed, and particular attention is paid to drill jigs, boring, profiling and milling fixtures and other devices in which the parts to be machined are located and fastened within the contrivances. All of the tools, fixtures and devices illustrated and described have been or are used for the actual production of work, such as parts of drill presses, lathes, patented machinery, typewriters, electrical apparatus, mechanical appliances, brass goods, composition parts, mould products, sheet metal articles, drop forgings, jewelry, watches, medals, coins, etc. Second edition. 531 pages. Price, \$4.50

### Henley's Encyclopedia of Practical Engineering and Allied Trades.

Edited by JOSEPH G. HORNER, A.M.I.Mech.E. This book covers the entire practice of Civil and Mechanical Engineering. The best known experts in all branches of engineering have contributed to these volumes. The Cyclopaedia is admirably well adapted to the needs of the beginner and the self-taught practical man, as well as the mechanical engineer, designer, draftsman, shop superintendent, foreman and machinist.

It is a modern treatise in five volumes. Handsomely bound in half morocco, each volume containing nearly 500 pages, with thousands of illustrations, including diagrammatic and sectional drawings with full explanatory details.

Price, \$30.00. For the complete set of five volumes.

## THE WHOLE FIELD OF MECHANICAL MOVEMENTS COVERED BY MR.

### HISCOX'S TWO BOOKS

We publish two books by Gardner D. Hiscox that will keep you from "inventing" things that have been done before, and suggest ways of doing things that you have not thought of before. Many a man spends time and money, pondering over some mechanical problem, only to learn, after he has solved the problem, that the same thing has been accomplished and put in practice by others long before. Time and money spent in an effort to accomplish what has already been accomplished are time and money lost. The whole field of mechanics, every known mechanical movement, and practically every device is covered by these two books. If the thing you want has been invented, it is illustrated in them. If it hasn't been invented, then you'll find in them the nearest things to what you want, some movement or device that will apply in your case, perhaps; or which will give you a key from which to work. No book or set of books ever published is of more real value to the inventor, draftsman or practical mechanic than the two volumes described below.

### Mechanical Movements, Powers and Devices.

By GARDNER D. HISCOX. This is a collection of 1,890 engravings of different mechanical motions and appliances, accompanied by appropriate text, making it a book of great value to the inventor, the draftsman, and to all readers with mechanical tastes. The book is divided into eighteen sections or chapters, in which the subject-matter is classified under the following heads: Mechanical Powers; Transmission of Power; Measurement of Power; Steam Power; Air Power Appliances; Electric Power and Construction; Navigation and Roads; Gearing; Motion and Devices; Controlling Motion; Horological; Mining; Mill and Factory Appliances; Construction and Devices; Drafting Devices; Miscellaneous Devices, etc. Fifteenth edition. 400 octavo pages.

Price, \$1.00

### Mechanical Appliances, Mechanical Movements and Novelties of Construction.

By GARDNER D. HISCOX. This is a supplementary volume to the one upon mechanical movements. Unlike the first volume, which is more elementary in character, this volume contains illustrations and descriptions of many combinations of motions and of mechanical devices and appliances found in different lines of machinery, each device being shown by a line drawing with a description showing its working parts and the method of operation. From the multitude of devices described and illustrated might be mentioned, in passing, such items as conveyors and elevators, Prony brakes, thermometers, various types of boilers, solar engines, oil-fuel burners, condensers, evaporators, Corliss and other valve gears, governors, gas engines, water motors of various descriptions, air ships, motors and dynamos, automobiles and motor bicycles, railway lock signals, car couplers, link and gear motions, ball bearings, breech block mechanism for heavy guns, and a large accumulation of others of equal importance. 1,000 specially made engravings. 396 octavo pages. Fourth revised edition. Price, \$4.00

## **"Shop Kinks."**

By ROBERT GRIMSHAW. This shows special methods of doing work of various kinds, and releasing cost of production. Has hints and kinks from some of the largest shops in this country and Europe. You are almost sure to find some that apply to your work, and in such a way as to save time and trouble. 400 pages. Fifth edition. Cloth. **Price, \$3.00**

## **Machine Shop Tools and Shop Practice.**

By W. H. VANDERVOORT. A work of 555 pages and 673 illustrations, describing in every detail the construction, operation, and manipulation of both hand and machine tools. Includes chapters on filing, fitting, and scraping surfaces; on drills, reamers, taps, and dies; the lathe and its tools; planers, shapers, and their tools; milling machines and cutters; gear cutters and gear cutting; drilling machines and drill work; grinding machines and their work; hardening and tempering; gearing, belting, and transmission machinery; useful data and tables. Sixth edition. Cloth. **Price, \$4.50**

## **Model Making.**

By RAYMOND FRANCIS YATES. A new book for the mechanic and model maker. This is the first book of its kind to be published in this country and all those interested in model engineering should have a copy. The first eight chapters are devoted to such subjects as Silver Soldering, Heat Treatment of Steel, Lathe Work, Pattern Making, Grinding, etc. The remaining twenty-four chapters describe the construction of various models such as rapid fire naval guns, speed boats, model steam engines, turbines, etc.

This book must not be confused with those describing the construction of toys now on the market. It is a practical treatise on model engineering and construction. 400 pages. 301 illustrations. **Price, \$3.00**

## **The Modern Machinist.**

By JOHN T. USHER. This book might be called a compendium of shop methods, showing a variety of special tools and appliances which will give new ideas to many mechanics from the superintendent down to the man at the bench. It will be found a valuable addition to any machinist's library and should be consulted whenever a new or difficult job is to be done, whether it is boring, milling, turning, or planing, as they are all treated in a practical manner. Fifth edition. 320 pages, 250 illustrations. Cloth. **Price, \$2.50**

## **Threads and Thread Cutting.**

By COLVIN and STABEL. This clears up many of the mysteries of thread cutting, such as double and triple threads, internal threads, catching threads, use of hobs, etc. Contains a lot of useful hints and several tables. Third edition. **35 cents**

## **MARINE ENGINEERING**

### **The Naval Architect's and Shipbuilder's Pocket-book**

of Formulae, Rules, and Tables and Marine Engineer's and Surveyor's Handy Book of Reference. By CLEMENT MACKROW and LLOYD WOOLLARD. The eleventh revised and enlarged edition of this most comprehensive work has just been issued. It is absolutely indispensable to all engaged in the Shipbuilding Industry, as it condenses into a compact form all data and formulae that are ordinarily required. The book is completely up to date, including among other subjects a section on Aeronautics. 750 pages, limp leather binding.

**Price, \$6.00 net**

### **Marine Engines and Boilers, Their Design and Construction. The Standard Book.**

By DR. G. BAUER, LESLIE S. ROBERTSON and S. BRYAN DOWKIN. In the words of Dr. Bauer, the present work owes its origin to an oft felt want of a condensed treatise embodying the theoretical and practical rules used in designing marine engines and boilers. The need of such a work has been felt by most engineers engaged in the construction and working of marine engines, not only by the younger men, but also by those of greater experience. The fact that the original German work was written by the chief engineer of the famous Vulcan Works, Stettin, is in itself a guarantee that this book is in all respects thoroughly up-to-date, and that it embodies all the information which is necessary for the design and construction of the highest types of marine engines and boilers. It may be said that the motive power which Dr. Bauer has placed in the fast German liners that have been turned out of late years from the Stettin Works represent the very best practice in marine engineering of the present day. The work is clearly written, thoroughly systematic, theoretically sound; while the character of the plans, drawings, tables, and statistics is without reproach. The illustrations are careful reproductions from actual working drawings, with some well-executed photographic views of completed engines and boilers. 744 pages, 550 illustrations, and numerous tables. Cloth. **Price, \$16.00 net**

## **MANUAL TRAINING**

### **Economics of Manual Training.**

By LOUIS ROUILLON. The only book that gives just the information needed by all interested in manual training, regarding buildings, equipment and supplies. Shows exactly what is needed for all grades of the work from the Kindergarten to the High and Normal School. Gives itemized lists of everything needed and tells just what it ought to cost. Also shows where to buy supplies. Illustrated. Second edition. Cloth. **Price, \$2.00**

## MINING

### **Prospector's Field-Book and Guide.**

By H. S. OSBORN. 1920 edition, revised and enlarged by M. W. von Bernewitz. The last edition of this volume was published in 1910. It and the previous seven editions were suitable for those times. The new ninth (1920) edition will be found suitable for the present time. While the old-time prospector will always be an important factor, the knowledge of and search for the common and rarer minerals is bringing out men who are trained to some degree. In the field they need a handy and suggestive pocket-book containing hints on prospecting—where to search and how to test—couched in simple terms. The chapter on preliminary instructions covers the fundamentals of a study of the earth's crust. Then follow discussions on practical mineralogy, crystallography, the value of the blowpipe in prospecting, surveying, and chemical tests in the field. Separate chapters are given to the precious and base metals, also to the non-metallic minerals. The chapter on the non-ferrous or alloy group of minerals is entirely new, while the section on oil has been expanded. Surface indications for copper receive full attention. The chapter on gems has been rewritten and matters concerning gemstones used for industrial purposes, such as abrasives, included. A general chapter covers many useful minerals and salts. An important guide and suggestive aid throughout the new book are the many brief descriptions of ore deposits of all minerals occurring in scattered parts of the world. No other prospector's book contains this class of information. In the appendix will be found numbers of useful tables, and a complete glossary of mining and mineralogical terms. The ninth edition of Osborn's "Prospector's Field Book and Guide" will be found up to date, worth while, and full value for the money asked. Flexible fabrikoid. 375 pages. 57 illustrations. 1920 edition. **Price, \$3.00**

## PATTERN MAKING

### **Practical Pattern Making.**

By F. W. BARROWS. This book, now in its second edition, is a comprehensive and entirely practical treatise on the subject of pattern making, illustrating pattern work in both wood and metal, and with definite instructions on the use of plaster of paris in the trade. It gives specific and detailed descriptions of the materials used by pattern makers and describes the tools; both those for the bench and the more interesting machine tools; having complete chapters on the lathe, the circular saw and the band saw. It gives many examples of pattern work, each one fully illustrated and explained with much detail. These examples, in their great variety, offer much that will be found of interest to all pattern makers, and especially to the younger ones, who are seeking information on the more advanced branches of their trade. Containing nearly 350 pages and 170 illustrations. Second edition, revised and enlarged. **Price, \$2.50**

## PERFUMERY

### **Henley's Twentieth Century Book of Receipts, Formulas and Processes.**

Edited by G. D. HISCOX. The most valuable techno-chemical receipt book published. Contains over 10,000 practical receipts, many of which will prove of special value to the perfumer. **Price, \$4.00**

### **Perfumes and Cosmetics, Their Preparation and Manufacture.**

By G. W. ASKINSON, Perfumer. A comprehensive treatise, in which there has been nothing omitted that could be of value to the perfumer or manufacturer of toilet preparations. Complete directions for making handkerchief perfumes, smelling-salts, sachets, fumigating pastiles; preparations for the care of the skin, the mouth, the hair, cosmetics, hair dyes and other toilet articles are given, also a detailed description of aromatic substances; their nature, tests of purity, and wholesale manufacture, including a chapter on synthetic products, with formulas for their use. A book of general, as well as professional interest, meeting the wants not only of the druggist and perfume manufacturer, but also of the general public. Fourth edition much enlarged and brought up-to-date. Nearly 400 pages, illustrated. **\$5.00**

## PLUMBING

### **Standard Practical Plumbing.**

By R. M. STARBUCK. This is a complete treatise and covers the subject of modern plumbing in all its branches. It treats exhaustively on the skilled work of the plumber and the theory underlying plumbing devices and operations, and commends itself at once to anyone working in any branch of the plumbing trade. A large amount of space is devoted to a very complete and practical treatment of the subjects of hot water supply, circulation and range boiler work. Another valuable feature is the special chapter on drawing for plumbers. The illustrations, of which there are three hundred and forty-seven, one hundred being full-page plates, were drawn expressly for this book and show the most modern and best American practice in plumbing construction. 6½ x 9¼. Cloth, 406 pages, 347 illustrations. **Price, \$3.50**

### **Mechanical Drawing for Plumbers.**

By R. M. STARBUCK. A concise, comprehensive and practical treatise on the subject of mechanical drawing in its various modern applications to the work of all who are in any way connected with the plumbing trade. Nothing will so help the plumber in estimating and in explaining work to customers and workmen as a knowledge of drawing, and to the workman it is of inestimable value if he is to rise above his position to positions of greater responsibility. 150 illustrations. **Price, \$2.00**

## **Modern Plumbing Illustrated.**

By R. M. STARBUCK. The author of this book, Mr. R. M. Starbuck, is one of the leading authorities on plumbing in the United States. The book represents the highest standard of plumbing work. A very comprehensive work, illustrating and describing the drainage and ventilation of dwellings, apartments and public buildings. The very latest and most approved methods in all branches of sanitary installation are given. The standard book for master plumbers, architects, builders, plumbing inspectors, boards of health, boards of plumbing examiners and for the property owner, as well as the workman and apprentice. It contains fifty-seven entirely new and large full pages of illustrations with descriptive text, all of which have been made specially for this work. These plates show all kinds of modern plumbing work. Each plate is accompanied by several pages of text, giving notes and practical suggestions, sizes of pipe, proper measurements for setting up work, etc. Suggestions on estimating plumbing construction are also included. 407 octavo pages, fully illustrated by 57 full-page engravings. **Price, \$5.00**

## **RECIPE BOOK**

### **Henley's Twentieth Century Book of Recipes, Formulas and Processes.**

Edited by GARDNER D. HISCOX. The most valuable technological formula book published, including over 10,000 selected scientific, chemical, technological and practical recipes and processes. This book of 800 pages is the most complete book of recipes ever published, giving thousands of recipes for the manufacture of valuable articles for everyday use. Hints, helps, practical ideas and secret processes are revealed within its pages. It covers every branch of the useful arts and tells thousands of ways of making money and is just the book everyone should have at his command. The pages are filled with matters of intense interest and immeasurable practical value to the photographer, the perfumer, the painter, the manufacturer of glues, pastes, cements and mucilages, the physician, the druggist, the electrician, the dentist, the engineer, the foundryman, the machinist, the potter, the tanner, the confectioner, the chirpologist, the manufacturer of chemical novelties and toilet preparations, the dyer, the electroplater, the enameler, the engraver, the provisioner, the glass worker, the goldbeater, the watchmaker and jeweler, the ink manufacturer, the optician, the farmer, the dairyman, the paper maker, the metal worker, the soap maker, the veterinary surgeon, and the technologist in general. A book to which you may turn with confidence that you will find what you are looking for. A mine of information up-to-date in every respect. Contains an immense number of formulas that every one ought to have that are not found in any other work. 1920 edition. Cloth binding. **Price, \$4.00**

## **RUBBER**

### **Henley's Twentieth Century Book of Receipts, Formulas and Processes.**

Edited by GARDNER D. HISCOX. Contains upward of 10,000 practical receipts, including among them formulas on artificial rubber. **Price, \$4.00**

### **Rubber Hand Stamps and the Manipulation of India Rubber.**

By T. O'CONNOR SLOANE. This book gives full details of all points, treating in a concise and simple manner the elements of nearly everything it is necessary to understand for a commencement in any branch of the India rubber manufacture. The making of all kinds of rubber hand stamps, small articles of India rubber, U. S. Government composition, dating hand stamps, the manipulation of sheet rubber, toy balloons, India rubber solutions, cements, blackings, renovating varnish, and treatment for India rubber shoes, etc.; the hektograph stamp inks, and miscellaneous notes, with a short account of the discovery, collection and manufacture of India rubber are set forth in a manner designed to be readily understood, the explanation being plain and simple. Third edition. 175 pages, illustrated. **Price, \$1.25**

## **SAWS**

### **Saw Filing and Management of Saws.**

By ROBERT GRIMSHAW. A practical hand book on filing, gumming, swaging, hammering and the brazing of band saws, the speed, work, and power to run circular saws, etc. A handy book for those who have charge of saws, or for those mechanics who do their own filing, as it deals with the proper shape and pitches of saw teeth of all kinds and gives many useful hints and rules for gumming, setting, and filing, and is a practical aid to those who use saws for any purpose. Third edition, revised and enlarged. Illustrated. **Price, \$1.50**

## **SCREW CUTTING**

### **Threads and Thread Cutting.**

By COLVIN and STABLE. This clears up many of the mysteries of thread cutting, such as double and triple threads, internal threads, catching threads, use of hobs, etc. Contains a lot of useful hints and several tables. Third edition. **35 cents**

## **STEAM ENGINEERING**

### **Horse-power Chart.**

Shows the horse-power of any stationary engine without calculation. No matter what the cylinder diameter or stroke; the steam pressure or cut-off; the revolutions, or whether condensing or non-condensing, it's all there. Easy to use, accurate, and saves time and calculations. Especially useful to engineers and designers. **Price, 50 cents**

### Steam Engine Troubles.

By H. HAMKENS. It is safe to say that no book has ever been published which gives the practical engineer such valuable and comprehensive information on steam engine design and troubles. There are descriptions of cylinders, valves, pistons, frames, pillow blocks and other bearings, connecting rods, wristplates, dashpots, reachrods, valve gears, governors, piping, throttle and emergency valves, safety stops, flywheels, oilers, etc. If there is any trouble with these parts, the book gives you the reasons and tells how to remedy them. 350 pages, 276 illustrations. **Price, \$2.50**

### American Stationary Engineering.

By W. E. CRANE. A new book by a well-known author. Begins at the boiler room and takes in the whole power plant. Contains the result of years of practical experience in all sorts of engine rooms and gives exact information that cannot be found elsewhere. It's plain enough for practical men and yet of value to those high in the profession. Has a complete examination for a license. Third edition revised and enlarged. 345 pages. 131 illustrations. Cloth. **Price, \$2.50**

### Steam Engine Catechism.

By ROBERT GRIMSHAW. This volume of 413 pages is not only a catechism on the question and answer principle, but it contains formulas and worked-out answers for all the steam problems that appertain to the operation and management of the steam engine. Sixteenth edition. **Price, \$2.00**

### Boiler Room Chart.

By GEO. L. FOWLER. A chart—size 14 x 28 inches—showing in isometric perspective the mechanism belonging in a modern boiler room. The various parts are shown broken or removed, so that the internal construction is fully illustrated. Each part is given a reference number, and these, with the corresponding name, are given in a glossary printed at the sides. **Price, 25 cents**

### Engine Runner's Catechism.

By ROBERT GRIMSHAW. Tells how to erect, adjust and run the principal steam engines in use in the United States. The work is of a handy size for the pocket. To young engineers this catechism will be of great value, especially to those who may be preparing to go forward to be examined for certificates of competency; and to engineers generally it will be of no little service, as they will find in this volume more really practical and useful information than is to be found anywhere else within a like compass. 387 pages. Seventh edition. **Price, \$2.00**

### Modern Steam Engineering in Theory and Practice.

By GARDNER D. HISCOX. This is a complete and practical work issued for stationary engineers and firemen dealing with the care and management of boilers, engines, pumps, superheated steam, refrigerating machinery, dynamos, motors, elevators, air compressors, and all other branches with which the modern engineer must be familiar. Nearly 200 questions with their answers on steam and electrical engineering, likely to be asked by the examining board, are included. Third edition. 487 pages, 405 engravings. Cloth. **Price, \$3.50**

### Steam Engineer's Arithmetic.

By COLVIN-CHENEY. A practical pocket book for the steam engineer. Shows how to work the problems of the engine room and shows "why." Tells how to figure horse-power of engines and boilers; area of boilers; has tables of areas and circumferences; steam tables; has a dictionary of engineering terms. Puts you onto all of the little kinks in figuring whatever there is to figure around a power plant. Tells you about the heat unit; absolute zero; adiabatic expansion; duty of engines; factor of safety; and 1,001 other things; and everything is plain and simple—not the hardest way to figure, but the easiest. Second edition. **Price, 75 cents**

## STEAM HEATING and VENTILATING

### Practical Steam, Hot-Water Heating and Ventilation.

By A. G. KING. This book has been prepared for the use of all engaged in the business of steam, hot-water heating and ventilation. Tells how to get heating contracts, how to install heating and ventilating apparatus, the best business methods to be used, with "Tricks of the Trade" for shop use. Rules and data for estimating radiation and cost and such tables and information as make it an indispensable work for everyone interested in steam, hot-water heating and ventilation. It describes all the principal systems of steam, hot-water, vacuum, vapor and vacuum-vapor heating, together with the new accelerated systems of hot-water circulation, including chapters on up-to-date methods of ventilation and the fan or blower system of heating and ventilation. Second edition. 367 pages, 300 detailed engravings. Cloth. **\$3.50**

### 500 Plain Answers to Direct Questions on Steam, Hot-Water, Vapor and Vacuum Heating Practice.

By ALFRED G. KING. This work, just off the press, is arranged in question and answer form; it is intended as a guide and text-book for the younger inexperienced fitter and as a reference book for all fitters. All long and tedious discussions and descriptions formerly considered so important have been eliminated, and the theory and laws of heat and the various old and modern methods and appliances used for heating and ventilating are treated in a concise manner. This is the standard Question and Answer examination book on Steam and Hot Water Heating, etc. 200 pages, 127 illustrations. Octavo. Cloth. **Price, \$2.00**

## STEEL

### Hardening, Tempering, Annealing and Forging of Steel.

By J. V. WOODWORTH. A book containing special directions for the successful hardening and tempering of all steel tools. Milling cutters, taps, thread dies, reamers, both solid and shell, hollow mills, punches and dies, and all kinds of sheet-

metal working tools, shear blades, saws, fine cutlery and metal-cutting tools of all descriptions, as well as for all implements of steel, both large and small, the simplest, and most satisfactory hardening and tempering processes are presented. 320 pages, 250 illustrations. Fourth edition. Cloth. **Price, \$3.00**

### **Steel: Its Selection, Annealing, Hardening and Tempering.**

By E. R. MARKHAM. This work was formerly known as "The American Steel Worker," but on the publication of the new, revised edition, the publishers deemed it advisable to change its title to a more suitable one. This is the standard work on hardening, tempering, and annealing steel of all kinds. This book tells how to select, and how to work, temper, harden, and anneal steel for everything on earth. It is the standard book on selecting, hardening, and tempering all grades of steel. 400 pages. Very fully illustrated. Fourth edition. **Price, \$3.00**

## **TRACTORS**

### **The Modern Gas Tractor.**

By VICTOR W. PAGÉ. A complete treatise describing all types and sizes of gasoline, kerosene, and oil tractors. Considers design and construction exhaustively, gives complete instruction for care, operation and repair, outlines all practical applications on the road and in the field. The best and latest work on farm tractors and tractor power plants. A work needed by farmers, students, blacksmiths, mechanics, salesmen, implement dealers, designers, and engineers. Second edition revised and much enlarged. 504 pages. Nearly 300 illustrations and folding plates. **Price, \$3.00**

## **TURBINES**

### **Marine Steam Turbines.**


By DR. G. BAUER and O. LASCHKE. Assisted by E. Ludwig and H. Vogel. Translated from the German and edited by M. G. S. Swallow. The book is essentially practical and discusses turbines in which the full expansion of steam passes through a number of separate turbines arranged for driving two or more shafts, as in the Parsons system, and turbines in which the complete expansion of steam from inlet to exhaust pressure occurs in a turbine on one shaft, as in the case of the Curtis machines. It will enable a designer to carry out all the ordinary calculation necessary for the construction of steam turbines, hence it fills a want which is hardly met by larger and more theoretical works. Numerous tables, curves and diagrams will be found, which explain with remarkable lucidity the reason why turbine blades are designed as they are, the course which steam takes through turbines of various types, the thermodynamics of steam turbine calculation, the influence of vacuum on steam consumption of steam turbines, etc. In a word, the very information which a designer and builder of steam turbines most requires. Large octavo, 214 pages. Fully illustrated and containing 18 tables, including an entropy chart. **Price, \$4.00 net**

**The Most Valuable Techno-Chemical Recipe Book Ever Offered to the Public!**

## **Henley's Twentieth Century Book of RECIPES, FORMULAS AND PROCESSES**

**Price \$4.00**

THIS book of 800 pages is the most complete Book of Recipes ever published, giving thousands of recipes for the manufacture of valuable articles for every-day use. Hints, Helps,



Practical Ideas and Secret Processes are revealed within its pages. It covers every branch of the useful arts and tells thousands of ways of making money and is just the book everyone should have at his command.

The pages are filled with matters of intense interest and immeasurable practical value to the Photographer, the Perfumer, the Painter, the Manufacturer of Glues, Pastes, Cements and Mucilages, the Physician, the Druggist, the Electrician, the Dentist, the Engineer, the Foundryman, the Machinist, the Potter, the Tanner, the Confectioner, the Chiropodist, the Manufacturer of Chemical Novelties and Toilet Preparations, the Dyer, the Electroplater, the

Enameler, the Engraver, the Provisioner, the Glass Worker, the Goldbeater, the Watchmaker and Jeweler, the Ink Manufacturer, the Optician, the Farmer, the Dairyman, the Paper Maker, the Metal Worker, the Soap Maker, the Veterinary Surgeon and the Technologist in general.

A book to which you may turn with confidence that you will find what you are looking for. A mine of information, up-to-date in every respect. Contains an immense number of formulas that every one ought to have that are not found in any other work.

**10,000 Practical Formulas and Processes**  
**The Best Way to Make Everything**

**ONE USEFUL RECIPE WILL BE WORTH MORE THAN TEN TIMES THE PRICE OF THE BOOK**

(See page 35 for further description of the book.)

















12.

621.004 S102 c.1

course in mechanical drawing for sch



087 155 624

UNIVERSITY OF CHICAGO